



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
APR 3 - 1972 4-3-72
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Vaughan Thompson of Sterling Drilling Company has this date requested permission to plug the following described well:

Mr. Thompson guarantees payment of the plugging fee.

Operator's full Name: Singer-Fleischaker, Oil Company,

Complete Address: Box #663, Oklahoma City, Oklahoma.

Lease Name: Grimes Well No. 1-9

Location: GSE Sec. 9 Twp. 20 Rge. (E)(W) 40

County: Greeley Total Depth 2848 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Thompson was instructed to plug the well as follows:

413'--8 5/8" Surface casing, cement circulated.

Lay down DP, fill hole with heavy mud to 425' and set bridge with 2 sacks hulls and 30 Sx. cement. Fill hole to 40' set bridge with 1 sack hulls and 10 Sx. cement to bottom of cellar.

Very truly yours,

H. L. Nichols
Conservation Division Agent