



# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217

### VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Bob Sargent of Sargent's Casing Pulling Ser. has this date requested permission to plug the following described well:

Mr. Sargent guarantees payment of the plugging fee.

Operator's full Name: Dorchester Exploration, Incorporated,

Complete Address: 1204 Baughn Building, Midland, Texas.

Lease Name: Grimes Well No. 1

Location: CSW/1 Sec. 11 Twp. 20 Rge. (E)(W) 10

County: Greeley Total Depth 2858 Oil Well

Gas Well  Input Well  SWD Well  D & A  Lost Hole

Mr. Sargent was instructed to plug the well as follows:

420'--8 5/8" Surface casing, cement circulated.  
2857'--4 1/2" Production casing cemented on bottom with 150 Sx. Top of cement @ 2250'. Top of perforations @ 2740'.

Pump 1 sack hulls followed with 20 Sx. cement to bottom. Shogt 4 1/2" casing and pull to 475' there displace 40 Sx. cement thru 4 1/2".  
4 1/2", set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of cellar.

Very truly yours,

*A. L. Nichols*

Conservation Division Agent

RECEIVED  
FEB 4 1974  
CONSERVATION DIVISION  
Wichita, Kansas  
STATE CORPORATION COMMISSION