

State of Kansas



15-203-20014-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

APR 1 - 1974  
4-1-74  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Carroll Flemmons of Galaxy Oil Company has this

date requested permission to plug the following described well:

Mr. Flemmons guarantees payment of the plugging fee.

Operator's full Name: Galaxy Oil Company,

Complete Address: 918 Lamar Street, Wichita Falls, Texas.

Lease Name: Dierks Well No. 1

Location: CSE-SW Sec. 26Twp. 19 Rge. (E)(W) 38

County: Wichita Total Depth 2812' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Flemmons was instructed to plug the well as follows:

335'--10 3/4" Surface casing, cement circulated.  
2679'--7" OD casing cemented on bottom with 125 Sx. Open hole completion.

Set 7" wire line bridge plug below top of cement with 6' cement on top.  
Shoot off 7" casing, pull 1 joint and displace cement thru 7" to base of  
surface casing. Pull 7", set bridge and 10' cement to bottom of cellar.

Very truly yours,

W. L. Nichols  
Conservation Division Agent