

15-165.00320-0001

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

APR 7 1964

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Solar Oil Co

Complete Address: 1117 Union Natl Bk Bldg Wichita, Kans

Lease Name Littler Well No. 1

Location SE SE NW Sec. 20 Twp. 16 Rge. (E) (W) 19

County Rush Total Depth 3840

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Ace Pipe Pulling Co

Address: Great Bend, Kans License No. 2

Operation Completed: Hour 10AM Day 31 Month 3 Year 64

The Above well was plugged as follows:

8 5/8" 160' circulated with cement - 5 1/2" 3840' with 125 sax cement.
~~PB 3915 - Perf 3467'.~~

~~Sanded back to 3450', set 4 sax cement with dump bailer - pulled 3135' 5 1/2"~~
~~to 480', circulated hole with heavy gel mud through 5 1/2" - displaced 20 sax~~
~~cement through 5 1/2" at 480', heavy mud to 160', displaced 20 sax cement~~
~~through 5 1/2" at 160', heavy mud to 25', cement to 0'.~~

Mudding and cementing by Ace Pipe Pulling pump truck.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 4/9/64
INV. NO. 8908-u