

TATE OF KANSAS  
TATE CORPORATION COMMISSION  
30 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-02-3-117

API NUMBER 15-101-20,916-0000

LEASE NAME Dirreen

WELL NUMBER 1-A

2310 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 26 TWP. 16S RGE. 30W (E) or (W)

COUNTY Lane

Date Well Completed \_\_\_\_\_

Plugging Commenced 7-19-00

Plugging Completed 7-25-00

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Double Eagle Exploration, Inc.

ADDRESS 221 S. Broadway Suite 310, Wichita, Ks. 67202

PHONE (316) 264-0422 OPERATORS LICENSE NO. 6009

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on \_\_\_\_\_ (date)

by Kevin Strube (KCC District Agent's Name).

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 4600'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

RECEIVED  
STATE CORPORATION COMMISSION

8-9-00

AUG - 9 2000

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	350'	None
				4-1/2"	4599'	None

CONSERVATION DIVISION  
Wichita Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other plugging material was used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each section. Bridge @2600', dumped 4 sks. cement on top, shot pipe @2250' and 1250'. Ran 2" tubing to 1250'; pumped 10 sks. gel, 80 sks. cement and 200# hulls, pulled tubing to 625', pumped 400# hulls, 50 sks. cement and 100# hulls, pulled tubing out and topped off with 20 sks. cement, pumped 5 sks. cement on backside. 60/40 pos, 6% gel. Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Double Eagle Exploration, Inc.

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso

(Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 8th day of August 2000

[Signature]  
Notary Public

My Commission Expires: \_\_\_\_\_

