

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-101-21-271-6000

LEASE NAME Sharp "A"

WELL NUMBER 1

SPOT LOCATION C W/2 SE SW NE

SEC. 26 TWP. 16 RGE. 30 (E or W)

COUNTY Lane

Date Well Completed 1-11-86

Plugging Commenced 1-11-86

Plugging Completed 1-11-86

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Landmark Oil Exploration
ADDRESS 105 S. Broadway Suite 1040, Wichita, KS 67202

PHONE # (316) 265-8181 OPERATORS LICENSE NO. 6113

Character of Well D & A
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? District 1

Is ACO-1 filed? No If not, is well log attached? Yes

Producing formation N/A Depth to top _____ bottom _____ T.D. _____

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	334'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Spotted 50 sx cement @ 2245' thru drill pipe

Spotted 80 sx cement @ 1370' thru drill pipe

Spotted 40 sx cement @ 340' thru drill pipe

Spotted solid B.P. and 10 sx cement @ 40' thru drill pipe

Spotted 15 sx cement in rathole

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor White & Ellis Drilling, Inc. License No. 5420
Address 401 East Douglas, Suite 500, Wichita, Ks. 67202

STATE OF Kansas COUNTY OF Sedgwick, ss


Ernest Sifford (employee of operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Ernest Sifford

(Address) 401 E. Douglas, Suite 500
Wichita, Ks. 67202

SUBSCRIBED AND SWORN TO before me this 17th day of January, 1986
DAVID F. JAMIS
NOTARY PUBLIC
STATE OF KANSAS
My Ass't Exp. 6-10-87

David F. Jamis
Notary Public



15-101-21271-0000

WHITE

AND ELLIS DRILLING, Inc.

DRILLERS LOG

OPERATOR: Landmark Exploration
105 S. Broadway, Suite 1040
Wichita, Kansas 67202

CONTRACTOR: White & Ellis Drilling, Inc., 401 E. Douglas, Suite 500,
Wichita, Ks. 67202

Lease Name Sharp A Well No. 1

Sec. 26 T. 16S R. 30W Spot C W/2 SE SW NE

County Lane State Kansas Elevation

Casing Record:

Surface: 8 5/8 @ 334' with 2% gel
3%cc 200 sx.

Production: @ with sx.

Type Well: D & A Total Depth 4610'

Drilling Commenced 1-2-86 Drilling Completed 1-11-86

Formation	From	To	Tops
Cellar	0	7	
Sand	7	336	
Sand, Shale	336	1800	
Shale	1800	2575	
Shale, Sand	2575	2830	
Lime, Shale	2830	3338	
Shale, Lime, Sand	3338	3534	
Lime	3534	3735	