

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-101-20,569-0000

LEASE NAME Dickey #1

WELL NUMBER _____

SPOT LOCATION SW SE NE

SEC. 25 TWP. 16 SRGE. 30 W (E) or (W)

COUNTY Lane

Date Well Completed _____

Plugging Commenced 11/5/85

Plugging Completed 11/14/85

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Kelso Casing bought f/ Leith Operations, Inc.

ADDRESS Box 347, Chase, Ks. 67524

PHONE # (316) 938-2457 OPERATORS LICENSE NO. 6050

Character of Well _____
(Oil, Gas, D&A, SMD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom _____ T.D. 4573'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	282'	none
				4 1/2"	4572'	900'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from _____ feet to _____ feet each set.

Plugged bottom with sand to 4375' & 4 sacks cement. Pulled stretch & pipe parted. Pulled 650' of pipe. Checked hole, got to 400'. Tried to knock bridge out. Had pulling unit run 4 1/2' overshot. Hooked on to 4 1/2" casing, washed hole clean to 1200'. Shot pipe at 1200', 1038', & 900'. Laid pipe down.

Plugged well with 200 sacks cement, 5 gel & 100 sacks 60/40 poz 6% gel. Plugging complete.
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050

Address Box 347, Chase, Ks. 67524

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso

(employee of operator) or


(operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) Box 347, Chase, Ks. 67524

SUBSCRIBED AND SWORN TO before me this 10th day of December, 1985

Irene Hoover
Notary Public



My Commission expires: _____

12-12-85

Wichita, Kansas