

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Return Report to
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217

Lane _____ County, Sec. 25 Twp. 16 Rge. 30W (E) _____ (W)Location as "NE/CNWSW" or footage from lines NW SE NELease Owner Hinkle Oil CompanyLease Name Dickey #1 Well No. _____Office Address Wichita, Kansas 67202

Character of Well (completed as Oil, Gas or Dry Hole) _____


Date well completed _____ 19 _____

Application for plugging filed _____ 19 _____

Application for plugging approved _____ 19 _____

Plugging commenced 9/10/74 _____ 19 _____Plugging completed 9/13/74 _____ 19 _____Reason for abandonment of well or producing formation depleted.

If a producing well is abandoned, date of last production _____ 19 _____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yesLocate well correctly on above
Section FlatName of Conservation Agent who supervised plugging of this well NicholsProducing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4590 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	290	none
				5 1/2"	4559'	1479'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked hole, pushed plug to 4400' and sanded to 4350', dumped 5 sacks cement. Cleaned cellar, loaded hole, shot pipe at 1972', 1785', 1595', 1500', pulled 46 joints. Squeezed well with 5 sacks hulls, 30 sacks gel and 150 cu. ft. cement.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION
SEP 19 1974
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KELSO CASING PULLINGAddress CHASE, KANSASSTATE OF KANSAS COUNTY OF RICE ss.R. DARRELL KELSO

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell KelsoCHASE, KANSAS

(Address)

Subscribed and Sworn to before me this 17th day of September, 19 74

MARGARET MELCHER
NOTARY PUBLIC
Rice County, Kansas
My Commission Expires
Feb. 15, 1975

Margaret Melcher
Notary Public.

DRILLERS LOG

15101-20065-0000

#1 Dickey

CASING RECORD:
284.98' of new 8-5/8"
surface casing.

COMPANY: Hinkle Oil Company
CONTRACTOR: Strata Drilling, Inc.

DESCRIPTION: NW SE NE
Section 25-16S-30W
Lane County, Kansas

TOTAL DEPTH:
4590'

COMMENCED: August 4, 1973
COMPLETED: August 16, 1973

FORMATION	FROM	TO	REMARKS
Shale	0	1015	Ran 284.98' of new 8-5/8" surface casing; set and cemented at 290.98' with 180 sacks of quick set cement and 2% gel. Plug down at 12:50 A. M. August 5, 1973.
Sand	1015	1095	
Shale	1095	2368	
Shale & Lime	2368	3780	
Lime	3780	3806	
Lime & Chalk	3806	3915	
Lime, Shale & Chalk	3915	3960	
Lime	3960	4026	
Shale & Lime	4026	4100	
Lime	4100	4180	
Shale & Lime	4180	4245	
Lime	4245	4280	
Lime & Shale	4280	4352	
Lime	4352	4590	

ROTARY TOTAL DEPTH: 4590'

Ran six drill stem tests.

Ran electric log.

5 1/2" casing set and cemented at 4559' with 275 sacks of 60-40 pozmix, 12% salt. Plug down at 12:45 P. M. August 16, 1973.

STATE OF KANSAS)
COUNTY OF BARTON) ss.

I certify that this is a true and correct copy of the above log to the best of my knowledge.

STRATA DRILLING, INC.

Charles W. Steincamp
Charles W. Steincamp, President

Subscribed and sworn to before me this 17th day of August, 1973.

My Commission Expires:
December 14, 1973

Elaine H. Taylor
Elaine H. Taylor, Notary Public

RECEIVED
STATE CORPORATION COMMISSION
SEP 24 1974
CONSERVATION DIVISION
Wichita, Kansas