


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Rush County, Sec. 13 Twp. 16 Rge. 18 (E) W (W)

Location as "NE/CNW/SW" or footage from lines NW NW NW
Lease Owner Aylward Drilling Co.
Lease Name A. Hermann #1 Well No. _____
Office Address Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 4-28-58 _____ 19____
Plugging completed 5-1-58 _____ 19____
Reason for abandonment of well or producing formation _____



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3678 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	1135'	none
				5-1/2"	3672'	2983'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked the hole to 3445' and found it open.
Filled w/sand to 3400' and ran 4 sacks of cement. Pulled 5 1/2" casing. Mudded the hole to 400', set a 10' rock bridge and ran 15 sacks of cement. Mudded to 200', set rock bridge and ran 15 sacks of cement. Mudded to 35', set rock bridge and ran 10 sacks of cement to base of cellar.

RECEIVED
MAY 21 1958
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor West Supply Co., Inc.
Address Chase, Kansas

STATE OF KANSAS COUNTY OF RICE, ss.
PAUL W. HESSE (employee of owner) or (~~owner~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Paul W. Hesse
813 1st Natl. Bank Bldg.
(Address)

SUBSCRIBED AND SWORN to before me this 5th day of May, 1958
Thomas V. Duggin
Notary Public.

My commission expires 9-27-58

PLUGGING
FILE NO. SEC. 13 T. 16 R. 18W
BOOK PAGE 96 LINE 12

HERRMAN NO. 1

OLD WELL WORKOVER

Casing Records:
8 5/8" - 1135'
5 1/2" - 3672'

Company: Aylward Drilling Company

Location: NW NW NW 13-16-18W
Rush County, Kansas

Contractor: Aylward Drilling Company

Elevation: 2009' K.B.

Commenced: October 8, 1957

Completed: October 16, 1957

	<u>From</u>	<u>To</u>	<u>Remarks</u>
Arbuckle Chert	3579	3589	This well was a washdown from the old Iron Drilling Company Herrman #1
Arbuckle Dolomite	3589	3665	
Reagan Sand	3665	3673 T.D.	

GEOLOGICAL TOPS:

Heebner	3242
Toronto	3261
Lansing	3290
Reworked Sandy Arbuckle Chert	3577
" Arbuckle Dolomite	3589
Reagan Sand	3665

- DST 3571-80 Open 1 hr., shut in 20 min. Rec. 1285' SW w/sl. scum oil. IFP 35#, FFP 575# BHP 1060#.
- DST 3581-89 Open 1 hr., shut in 20 min. Rec. 35' mud w/few specks oil. IFP 35#, BHP 1200#.
- DST 3430-65 Open 1 hr., shut in 20 min., Rec. 1100' gas, 112' OCM. ISIP 1140#, IFP 15#, FFP 55#, BHP 655#.
- DST 3580-3665 Open 40 min., shut in 20 min. Rec. 2360' SW w/few drops oil on top. IFP 405#, FFP 925#, BHP 925#.
- DST 3466-3503 Open 1/4 hr., shut in 20 min., Rec. 10' oil specked salty mud. ISIP 0#, IFP 0#, FFP 0#, BHP 35#.
- DST 3262-3352 Open 2 hr. shut in 20/20 min. Rec. 210' muddy SW w/scum oil on top. ISIP 875#, IFP 35#, FFP 105#, BHP 875#.
- DST 3430-65 Open 2 hr., shut in 30 min. Rec. 960' gas, 40' sl. OC acid water and 200' very heavily OCM, 25 to 50% oil. IFP 35#, FFP 135#, BHP 230#.

I hereby certify that this is a true and correct copy of the above log to the best of my knowledge.

Paul W. Hesse

Subscribed and sworn to before me this 20th day of May, 1958.

STATE COMMISSIONER

Duane Jessup
DUANE JESSUP Notary Public

My commission expires December 11, 1961.

MAY 21 1958

CONSERVATION DIVISION

PLUGGING
FILE SEC 13-16-18W
BOOK PAGE 96 LINE 12