

15-165-00124.0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

OR
FORMATION PLUGGING RECORD

Strike out upper line
when reporting plug-
ging off formations.

Rush County. Sec. 13 Twp. 16S Rge. (E) 18 (W)

Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines.....

Lease Owner..... Iron Drilling Company et al

Lease Name..... Herrman Well No. 1

Office Address..... 1206 Philtower Building Tulsa, Oklahoma

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed..... January 11 1947

Application for plugging filed..... January 11 1947

Application for plugging approved..... January 11 1947

Plugging commenced..... January 11 1947

Plugging completed..... January 11 1947

Reason for abandonment of well or producing formation..... Dry Hole

If a producing well is abandoned, date of last production..... 19.....

Was permission obtained from the Conservation Division or its agents before plugging was com-
menced?..... Yes

Name of Conservation Agent who supervised plugging of this well..... H. W. Karr

Producing formation..... Depth to top..... Bottom..... Total Depth of Well. 3579 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS


CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				13"	166'	None
				9-5/8"	1137'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from..... feet to..... feet for each plug set.

Circulated heavy mud top to bottom
Set wood plug at 300' and set 15 sax cement
Filled hole to 15' with heavy mud
Set wood plug at 15' and filled hole to bottom of cellar
with 10 sax cement

PLUGGING
FILE SEC 13 T16 R18
BOOK PAGE 93 LINE 6



(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to..... Iron Drilling Company
Address..... 1206 Philtower Building Tulsa, Okla.

STATE OF Oklahoma, COUNTY OF Tulsa, SS.
Horriek Babcock (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Horriek Babcock

1206 Philtower Building, Tulsa, Okla.
(Address)

SUBSCRIBED AND SWORN TO before me this 18th day of January, 19 47

B. Michal
Notary Public.

My commission expires Feb. 26, 1948

DRILLING RECORD

Well No. 1 Herrman
NW Corner Sec. 13-16S-18W
Rush County, Kansas

Casing Record

1137' of 8 5/8" OD Surface
pipe cemented with 600 sax.

Work Commenced 12/16/46
Drilling Commenced 12/18/46
Drilling Completed 1/10/47
Work Completed 1/11/47

No Oil String - Dry Hole

WELL LOG

Surface Clay	0 to 19
Post Rock & Shale	19 to 158
Shale	158 to 300
Shale & Shells	300 to 495
Sand	495 to 758
Sand & Shale	758 to 807
Sand	807 to 841
Shale	841 to 845
Shale & Shells	845 to 855
Shale	855 to 960
Red Bed	960 to 1025
Red Bed & Shells	1025 to 1125
Lime & Shells	1125 to 1135
Anhydrite	1135 to 1162
Red Bed & Shale	1162 to 1355
Shale & Shells	1355 to 1570
Shale	1570 to 1800
Lime	1800 to 1865
Shale & Shells	1865 to 1900
Lime	1900 to 1965
Lime & Shale	1965 to 2025
Lime	2025 to 2120
Broken Lime	2120 to 2205
Lime	2205 to 2240
Lime & Shale	2240 to 2280
Broken Lime	2280 to 2537
Shale	2537 to 2565
Broken Lime	2565 to 2600
Shale & Lime	2600 to 2770
Shale	2770 to 2968
Lime	2968 to 2979
Shale	2979 to 2995
Lime	2995 to 3087
Lime & Shale	3087 to 3195
Lime	3195 to 3260
Shale	3260 to 3273
Lime	3273 to 3530
Shale & Lime	3530 to 3545
Cherty Conglomerate	3545 to 3568
Sand	3568 to 3579 TD Plugged & Abandoned 1/11/47

C E R T I F I C A T I O N

State of Oklahoma, County of Tulsa, SS

I, Herrick Babcock, Partner of Iron Drilling Company, Certify that the accompanying is a true and correct log of the above described well.

Signature Herrick Babcock

Subscribed to and Sworn before me this 18th day of January, 1947.

B. Michal
Notary Public

My commission expires Feb. 28, 1948

PLUGGING
FILE NO. 13-16-18W
BOOK PAGE 92 ONE 6

