

15-165-30118-0000

Form CP-3
Rev. 6-9-67

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
APR 11 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Frontier Oil Company,

Complete Address 1720 Wichita Plaza, Wichita, Kansas.

Lease Name Allen Well No. B-1

Location NW-NW-NE Sec. 32 Twp. 16 Rge. (E) (W) 16

County Rush Total Depth 3590'

Abandoned Oil Well Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Allied Cementing Company, Incorporated,

Address Box #207, Russell, Kansas. License No.

Operation Completed: Hour 2:30 PM Day 8 Month 4 Year 1968

The above well was plugged as follows:

312'--8 5/8" Surface pipe, cement circulated with 240 Sx.
3589'--4 1/2" Production casing cemented on bottom with 275 Sx. 4 1/2" squeezed from the
Anhydrite to surface. Well plugged back to 3050'. Top perforations from 3005' to 3014'.
Squeezed 4 1/2" initially with 10 Sx. cement then 30 sacks gel and finally 120 Sx. cement
Plus 6% gel. Maximum pump-in pressure 800#. Final shut-in pressure 200#.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: M. L. Nichols
Well Plugging Supervisor

DATE 4/11/68
INV. NO. 9558-U