

15-165-31846-0000

**KANSAS
STATE CORPORATION COMMISSION**

CONSERVATION DIVISION AGENT'S REPORT

MAY 13 1960
CONSERVATION DIVISION
Wichita, Kansas

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. _____ County: Rush

Location: NW NE NE Sec. 11 Twp. 16 Rge. 18 (E) (W)

Name of Field: _____ Total Depth: 3610

I have this date completed supervision of plugging of:

Lease Name: Werth Well No. 1

Operator's Full Name: Imperial Oil of Kansas

Complete Address: 780 4th Natl Bk Bldg Wichita, Kans

Plugging Contractor: Southwest Casing pulling Co

Address: Great Bend, Kans License No. 399

Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D & A

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No

If yes how long? _____ Reason: _____

Operation Completed: Hour 5PM Day 7 Month 5 Year 60

The above well was plugged as follows:

8 5/8" 1130' circulated with cement - 4 1/2" 3609' with 100 sax cement behind,
PB to 3552' - perforated 3544' -

Filled with sand to 3530', set 4 sax cement with dump bailer, pulled
3100' 4 1/2" to 450', circulated hole with heavy mud through 4 1/2" Gel Mud -
displaced 20 sax cement through 4 1/2" at 450', heavy mud to 180', displaced
20 sax cement through 4 1/2" at 180', heavy mud to 35', set bridge and 10
sax cement to bottom cellar.

Mudding and cementing by Halliburton Co.

Signed: *E. J. Perry*
Conservation Division Agent

Reviewed: *J. Lewis Brock*
Field Supervisor

Remarks:

INVOICED
DATE 5/16/60
INV. NO. 1360-w