

State of Kansas



15:203-20072-0000

## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)RECEIVED  
STATE CORPORATION COMMISSION

APR 1 - 1974

CONSERVATION DIVISION  
Wichita, KansasJ. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Carroll Flemmons of Galaxy Oil Company has this  
date requested permission to plug the following described well:Mr. Flemmons guarantees payment of the plugging fee.Operator's full Name: Galaxy Oil Company.Complete Address: 918 Lamar Street, Wichita Falls, Texas.Lease Name: Foster Well No. 1Location: CNE-NE Sec. 6 Twp. 19 Rge. (E)(W) 37County: Wichita Total Depth 2920' Oil Well Gas Well  Input Well  SWD Well  D & A X Lost Hole Mr. Flemmons was instructed to plug the well as follows:311'--8 5/8" Surface casing, cement circulated.2920'--4 1/2" casing cemented on bottom with 175 Sx. Top perforations from  
2807' to 2809'.Set Welex wire line bridge plug @ 1200' and 10' cement on top with dump  
bailer. Shoot & pull 1 joint 4 1/2" casing and displace cement thru 4 1/2" to  
base of surface. Pull 4 1/2", set bridge and 10' cement to base of cellar.

Very truly yours,

  
Conservation Division Agent