

State of Kansas



15-203-20012-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
APR 1 - 1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Carroll Flemmons of Galaxy Oil Company has this date requested permission to plug the following described well:

Mr. Flemmons guarantees payment of the plugging fee.

Operator's full Name: Galaxy Oil Company,

Complete Address: 918 Lamar Street, Wichita Falls, Texas.

Lease Name: Nuss Well No. 1

Location: CNW-NW Sec. 1 Twp. 18 Rge. (E)(W) 37

County: Wichita Total Depth 2842' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Flemmons was instructed to plug the well as follows:

310'--10 3/4" Surface casing, cement circulated.
2726'--7" OD casing cemented on bottom with 125 Sx. (Open Hole Completion).

Set 7" Welex wire line plug with 6' cement on top below top of cement on 7". Shoot off 7" casing, pull 1 joint and displace cement thru 7" to base of surface casing. Pull 7", set bridge and 10' cement to bottom of cellar.

Very truly yours,

W. L. Fickels
Conservation Division Agent