

State of Kansas



15-203-20018-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)RECEIVED
STATE CORPORATION COMMISSION

APR 1 - 1974

CONSERVATION DIVISION
Wichita, KansasJ. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Carroll Flemmons of Galaxy Oil Company has this
date requested permission to plug the following described well:Mr. Flemmons guarantees payment of the plugging fee.Operator's full Name: Galaxy Oil Company,Complete Address: 918 Lamar Street, Wichita Falls, Texas.Lease Name: Evans Well No. 1Location: CNE-NE Sec. 27 Twp. 18 Rge. (E)(W)37County: Wichita Total Depth 3035' Oil Well Gas Well Input Well SWD Well D & A X Lost Hole Mr. Flemmons was instructed to plug the well as follows:310'--8 5/8" Surface casing, cement circulated.3012'--4 1/2" casing cemented on bottom with 200 Sx. Top perforations from
2773' to 2784'.Set wire line bridge plug below top of cement and 10' cement on top.Shoot 4 1/2" casing, pull 1 joint and displace cement thru 4 1/2" to base of
surface. Pull 4 1/2", set bridge and 10' cement to base of cellar.

Very truly yours,

Conservation Division Agent