


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

WELL PLUGGING RECORD

NORTH

Locate well correctly on above
Section Plat

Rush County, Sec. 20 Twp. 16S Rge. (E) 18 (W)
Location as "NE/CNW/SW" or footage from lines SE SE SE
Lease Owner The Bay Petroleum Corporation
Lease Name Dachant Well No. 1
Office Address Box 513 Chase Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed February 12 19 54
Application for plugging filed (written) February 15 19 54
Application for plugging approved (oral) February 12 19 54
Plugging commenced February 12 19 54
Plugging completed February 12 19 54
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well _____

Producing formation Reagan sd (test) Depth to top 3568 Bottom _____ Total Depth of Well 3584 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				<u>8 5/8</u>	<u>123'</u>	<u>None</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud through drill pipe.
Put plug in top of pipe and pumped 100 sac of
cement into pipe by Globe Cementing Co.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Strain Drilling Co.,
Address Hays Kansas

STATE OF Kansas COUNTY OF Rice, ss.
Glen E. Armour (employee of owner) Strain Drilling Co.

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Glen E. Armour


(Address)

SUBSCRIBED AND SWORN to before me this 15 day of February, 19 54My commission expires May 20 1954

Notary Public.

24-7986-S 3-53-20M

cc/ T.C. Strain
Denver ofc
Wichita ofc



02-16-54

COMPANY: The Ray Petroleum Corp. 15-465-00185-0000

LEASE: Dechant # 1

SE 34 Sec. 20
Twp. 16S, Rge 18W
Rush County, Kansas.

ELEVATION: 2000 R. B.

NOTE: All meas Rotary Readings

Chase

0 30 Shale, Soil & Sand
30 123 Post Rock & Blue Shale
123 173 Blue Shale
173 550 Shale & Shells
550 823 D.K.T. Sand
823 875 Shale & Shells
875 1083 Shale & Redbed
1083 1159 Redbed & Shale
1159 1202 Anhydrite
1202 1310 Shale & Shells
1310 1390 Shale & Shells
1390 1520 Lime & Shale
1520 1640 Lime & Shale
1640 1810 Salt & Shale
1810 1835 Shale & Lime
1835 1965 Lime & Shale
1965 2010 Lime
2010 2060 Lime & Shale
2060 2160 Lime & Shale
2160 2180 Lime
2180 2210 Lime
2210 2285 Lime
2285 2400 Lime
2400 2455 Lime
2455 2595 Lime & Shale
2595 2705 Lime & Shale
2705 2765 Shale & Lime
2765 2845 Shale & Lime
2845 2900 Shale & Lime
2900 2970 Lime & Shale
2970 3030 Lime
3030 3090 Lime
3090 3120 Lime
3120 3170 Lime
3170 3195 Lime
3195 3250 Lime
3250 3290 Lime
3290 3301 Lime
3301 3330 Lime
3330 3350 Lime
3350 3380 Lime
3380 3395 Lime
3395 3450 Lime
3450 3460 Lime
3460 3510 Lime
3510 3548 Lime & Shale

3548 3560 Conglomerate
3560 3577 Conglomerate
3577 3584 C'tzite
3584 (Total Depth)

COMMENCED: 1-28-54
COMPLETED: 2-12-54

CASING RECORD:

10 3/4" Surface Casing set : 163' w/135 Sacks
of cement by Sun Cementing Co.

D.S.T. By Globe Cementing Co.

3135-3170 Tool open 1 hr, 10 min. Recovered 10'
of rotary mud. 15 min. B.H.P. 1050#

D.S.T. By Lee Formation Testing Co.

3278-3301 Tool open 1 hr. Recovered 90' of
muddy salt water 20 min. B.H.P. 1060#

3306-3330 Tool open 1 hr. Weak blow for 4 min.
Recovered 5d of rotary mud. 20 min B.H.P. 0

D.S.T. By Globe Cementing Co.

3332-3380 Tool open 1 hr. Recovered 350' watery
mud. 20 min. B.H.P. 1145# I.P.P. 50# F.F.P. 205#

D.S.T. By Sun Cementing Co.

3422-3450 Tool open 1 hr. Weak blow 1 hr.
Recovered 144' Watery mud. 20 min. B.H.P. 775#

3572-3577 Tool open 2 hrs. Strong blow thru
test. Gas to surface in 22 min. Recovered
30' of mud. 30 min B.H.P. 1100#

Geologist: Don Brown.

TOPS:

Geological

Anhydrite 1158 (+842)
Topoka 2991 (-991)
Heebner 3232 (-1232)
Toronto 3250 (-1250)
K. C. 3277 (-1277)

Bess K. C. 3506 (-1506)
Conglomerate 3548 (-1548)
Sand R. 3571 (-1571)
C'tzite 3576 (-1576)
Total Depth 3584 (-1584)

STATE OF KANSAS) SS
COUNTY OF RUSH)

I hereby affirm that the above and foregoing is a true and correct copy of the log of
the Dechant # 1, located SE 34 Sec. 20, Twp 16S, Rge 18W Rush County, Kansas.

CONTRACTOR: Strain Drilling Company

PLUGGING

WELL NO. 20-16-18W

DATE 14 APR 4

BY:

T. C. Strain

T. C. Strain

Subscribed and sworn to before me this 15th day of February 1954.
My Commission expires March 26, 1956

Michael Schneider
Notary Public.