


15.165-00355.0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Rush County. Sec. 19 Twp. 16S Rge. (E) 18 (W)
Location as "NE/CNW/SW" or footage from lines 1980'FS & 1980'FW lines of
Lease Owner Continental Oil Company section
Lease Name Joe Suppes Well No. 1
Office Address Drawer 367, Plainville, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 4-8 19 63
Application for plugging filed 4-9 19 63
Application for plugging approved 4-9 (Verbal) 19 63
Plugging commenced 4-9 19 63
Plugging completed 4-9 19 63
Reason for abandonment of well or producing formation No commercial shows encountered.

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Mr. Eldon Petty
Producing formation None Depth to top _____ Bottom _____ Total Depth of Well 3668 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
<u>Topeka</u>	<u>Salt Water</u>	<u>3050'</u>	<u>3100'</u>	<u>13 3/8"</u>	<u>365'</u>	<u>None</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled with heavy mud to 340', and spotted 35 sacks of cement. Filled with heavy mud to 180', and spotted 35 sacks. Mudded to 35', and dumped 30 sacks of cement filling hole to surface.

RECEIVED
STATE CORPORATION

APR 11 1963

CONSERVATION
WICHITA, KAN.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Red Tiger Drilling Company
Address Wichita, Kansas

STATE OF Kansas, COUNTY OF Rooks, ss.
L. E. Powell (employee of owner) or (owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

ARC
State CRW File
(Signature) L. E. Powell
Drawer 367, Plainville, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 10th day of April, 19 63

My commission expires 12-2-65
Kenneth J. Querry Notary Public.

4/11/63
6883-W

DRILLERS LOG

Suppes No. 1

CASING RECORD: 13 3/8" @ 365'
w/350 sx cement

COMPANY: Continental Oil Company

CONTRACTOR: Red Tiger Drilling Co.

COMMENCED: March 29, 1963

COMPLETED: April 9, 1963

DESCRIPTION: C NE SW
19-16S-18W
Rush Co.,
Kansas

ELEVATION:

TOTAL DEPTH: 3668'

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Sod	0	30	
Shale & Shells	30	827	
Red Bed & Shale	827	1222	
Anhydrite	1222	1256	
Shale	1256	1290	
Shale & Shells	1290	1787	
Shale	1787	1958	
Lime & Shale	1958	3085	
Lime	3085	3566	
Lime & Shale	3566	3630	
Lime & Chert	3630	3668	

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

George A. Angle
George A. Angle

Subscribed and sworn to before me this 12th day of April, 1963.

Minnie V. Head
Notary Public

My Commission Expires:

11-17-66

CRB-drs 4-16-63

State Corp. Comm.
Kansas Geological Society
CRW
File

RECEIVED
STATE CORPORATION COMMISSION

APR 17 1963

CONSERVATION DIVISION
Wichita, Kansas