

Kansas Corporation Comm.
Wichita State Office Bldg.
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 165-21682 0000

LEASE NAME Urban "A"

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1
3960 Ft. from S Section Line
2310 Ft. from E Section Line

LEASE OPERATOR AFG Energy, Inc.

SEC. 25 TWP. 16S RGE. 18 (K) or (W)

ADDRESS P.O. Box 458 Hays, Kansas 67601

COUNTY Rush

PHONE# (913) 625-6374 OPERATORS LICENSE NO. 3456

Date Well Completed 11/6/95

Character of Well D&A

Plugging Commenced 2:00AM 11/6/95

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 6:00 AM 11/6/95

The plugging proposal was approved on 11/4/1995 (date)

by Steve Middleton Dodge City (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation None Depth to Top _____ Bottom T.D. 3640'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Put In
Topeka	Gassy Mud	0	1161	8 5/8	1161.38	None
Sand	Gas & Water					

RECEIVED
STATE CORPORATION COMMISSION
DEC 12 06 95
DEC - 3 1995
CONSERVATION DIVISION

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set
1st Plug @ 3580' W/40sks 10sks In Mouse Hole Circulated 1st Plug 15 Minutse with 51 Vis. Mud
2nd Plug @ 1190' W/50sks 15sks In Rat Hole Displaced plugs with mud
3rd Plug @ 500' W/40sks
4th Plug @ 40' W/10sks Total 165sks 60/40 Poz 6%Gel Completed @6:00AM 11/6/95 By Allied
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Discovery Drilling Co., Inc. License No. 31548

Address P.O. Box 763 Hays, Kansas 67601

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: AFG Energy, Inc.

STATE OF Kansas COUNTY OF ELLIS, ss.

Edgar L. Glassman

(Employee of Operator) or (Operator) above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed: the same are true and correct, so help me God.

(Signature) Edgar L. Glassman

(Address) P.O. Box 458 Hays, KS 67601

SUBSCRIBED AND SWORN TO before me this 5th day of Nov, 1995

Linda K. Franzen
Notary Public

Commission Expires: 2/5/96

