

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-101-20966-00-00
API NUMBER _____

LEASE NAME Cox B

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1

330 Ft. from S Section Line

640 Ft. from W Section Line

SEC. 35 TWP. 16 RGE. 30W (E) or (W)

LEASE OPERATOR Apollo Energies, Inc.

COUNTY Lane

ADDRESS 10378 N. Hwy. 281 Pratt, Kansas 67124

Date Well Completed _____

PHONE#(620) 672-9001 OPERATORS LICENSE NO. 30481

Plugging Commenced 6-14-01

Character of Well Oil

Plugging Completed 6-19-01

(Oil, Gas, D&A, SMD, Input, Water Supply Well)

The plugging proposal was approved on _____ (date)

by Mike Maier (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.O. 4640'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	369'	None
				4-1/2"	4240'	600'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other pl were used, state the character of same and depth placed, from feet to feet each s' Plugged off bottom with sand to 3800' and 4 sks. cement. Shot pipe @1240' and 600'. Ran 2" tubing to 1240', pumped 80 sks. cement, pulled up to 600', pumped 50 sks. cement, pulled up 390', pumped 50 sks. cement, pulled up to 30', pumped 30 sks. cement. 60/40 pos. 6% gel. Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License **RECEIVED**

KANSAS CORPORATION COMMISSION

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Apollo Energies, Inc. JUL 9 2001

STATE OF Kansas COUNTY OF Rice, ss. 7-9-01

CONSERVATION DIVISION

Mike Kelso (Employee of Operator or Contractor)
above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed t the same are true and correct, so help me God.

(Signature) Mike Kelso

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 6th day of July ~~XXX~~ 2001

Irene Herzberg
Notary Public

My Commission Expires: _____



Form 67
Revised 05-

OR