


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Rush County, Sec. 5 Twp. 16 Rge. 19 S/W
Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines



Locate well correctly on above
Section Plot

NE NE SE
Lease Owner Bill Witcraft
Lease Name Werth "B" Well No. 1
Office Address Box 811, Great Bend, Kansas 67530
Character of Well (Completed as Oil, Gas or Dry Hole)

dry hole
Date Well completed Feb. 22 19 81
Application for plugging filed Feb. 22 19 81
Application for plugging approved Feb. 22 19 81
Plugging commenced Feb. 22 19 81
Plugging completed Feb. 22 19 81
Reason for abandonment of well or producing formation

dry hole
If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey
Producing formation Depth to top Bottom Total Depth of Well 3690
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	326	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

1st plug 680 w/65 sx.
2nd plug 330 w/30 sx.
3rd plug 40 w/10 sx.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Woodman & Iannitti Drilling Co.

STATE OF KANSAS COUNTY OF SEDGWICK, SS.
K. T. Woodman (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) K. T. Woodman
1008 Douglas Bldg., Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 10th day of March, 19 81

My commission expires Feb. 11, 1984

Justina Chamberlain
Justina Chamberlain Notary Public.

MAR 11 1981

15-1165-20841-0000

K. T. WOODMAN
RES. PHONE 733-0418
OFF. PHONE 265-7650
WICHITA, KANSAS

D. J. IANNITTI
PHONE 792-2921
GREAT BEND, KANSAS

WOODMAN & IANNITTI DRILLING COMPANY
Rotary Drilling Contractors
1008 DOUGLAS BUILDING
104 S. BROADWAY
WICHITA, KANSAS 67202

March 10, 1981

Company;	Bill Witcraft
Farm;	Werth "B" #1
Location;	NE NE SE
Section;	5-16-19W
County;	Rush
Contractor;	Woodman & Iannitti Drilling Co.
Comm;	February 14, 1981
Compl;	February 22, 1981
Total Depth;	3690
Casing;	8 5/8 @ 326 w/200 sx.
Production;	D & A

Figures Indicate Bottom Of Formations;

326	Surface
630	Shale & sand
788	Redbed
949	Sand
1274	Redbed
1314	Anhy
2010	Shale
2225	Shale
2670	Shale & lime
3160	Shale & lime
3312	Lime
3390	Lime
3416	Kansas city
3541	Lime
3665	Lime
3690	Lime

I certify the above to be a true and correct copy of the drillers log to the best of my knowledge and belief.

Woodman & Iannitti Drilling Co.



K. T. Woodman

RECEIVED
CONSERVATION DIVISION

MAR 11 1981

CONSERVATION DIVISION
Wichita, Kansas