


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 North Market, Insurance Bldg.  
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above Section Flat

Rush County, Sec. 6 Twp. 16 Rge. 19 (E) W  
Location as "NE/CNW/SW" or footage from lines CNW NW  
Lease Owner Bill May Day Co Inc  
Lease Name Schu H. P. Well No. 1  
Office Address 2007 Polk St. Bend Ks  
Character of Well (completed as Oil, Gas or Dry Hole) Oil  
Date well completed 5 1965  
Application for plugging filed 12-2 1968  
Application for plugging approved 12-5 - Renewed 5-13-69 1968  
Plugging commenced May 14 1969  
Plugging completed May 14 1969  
Reason for abandonment of well or producing formation Making too much water  
If a producing well is abandoned, date of last production 71 1965  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey  
Producing formation Marmaton Depth to top 3658 Bottom 3668 Total Depth of Well 3685 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface	RECEIVED			8 5/8	305	0'
Reagan	STATE CORPORATION COMMISSION	3685	-	5 1/2	3685	0'
	JUL 31 1969					
	CONSERVATION DIVISION					
	Wichita, Kansas					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.


Rotary mud Hauled in with vacuum truck & circulated to fill hole thru 2" tubing. 25 sacks cement mixed & spotted 3500' - 3700' Filled 5 1/2" with cement from 700' to surface. Circulated back in surface (8 5/8") shut in pressure 200. Cut pipe 5 1/2" & 8 5/8" off 6' below ground level. Plugged with Halliburton pump truck Hays - Kansas

Name of Plugging Contractor Bill May Day Co Inc # 118  
Address 2007 Polk Great Bend Ks

STATE OF Kansas, COUNTY OF Barton, ss.  
George R. Walling (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Geo R. Walling  
Paradise, Kansas (Address)

Subscribed AND Sworn to before me this 30th day of July, 19 69



David H. Schauer  
Notary Public.

K-1165-30018-0000  
**KANSAS GEOLOGICAL SOCIETY**  
 KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU  
 KANSAS GEOLOGICAL SOCIETY BUILDING  
 508 EAST MURDOCK - WICHITA, KANSAS

COPY

COMPANY **MUIR-THOMPSON**  
 FARM **Schutte** NO. **1**

SEC. **6** T. **16** R. **19W**  
 LOC. **C NW NW**

TOTAL DEPTH **3695'**  
 COMM. **2-22-65** COMP. **5-13-65**  
 SHOT OR TREATED  
 CONTRACTOR **M-S-T**  
 ISSUED **12-2-67**

COUNTY **Rush**  
**KANSAS**

●			

CASING

20	10				
15	8 5/8	275'			
12	6				
13	5 1/2	3695'			

ELEVATION **2081 KB**  
 PRODUCTION Pmp **25 BOPD**  
 & **20% W. (Marm 3658-68) NEW**  
**PAY;**

FIGURES INDICATE BOTTOM OF FORMATIONS

COMPLETE DRILLERS LOG NOT AVAILABLE.

TOPS: SCOUT	SAMPLE
Topeka ?	3045
Heebner	3321
Lansing	3363
Marmaton	3642
Reagan	3686

RECEIVED  
 STATE CORPORATION COMMISSION  
 DEC 5 1968  
 CONSERVATION DIVISION  
 Wichita, Kansas