

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

Rush County. Sec. 21 Twp. 16 Rge. 19 (E) W (W)

Location as "NE/CNW%SW%" or footage from lines NW NW NW

Lease Owner Dreiling Oil, Inc.

Lease Name Brown Well No. 1

Office Address Route #2, Victoria, Kansas 67671

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 7-10, 71

Application for plugging filed 7-10, 71

Application for plugging approved 7-10, 71


Plugging commenced 7-10, 71

Plugging completed 7-10, 71

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Leo Massey

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Pipe				8 5/8"	230'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

- 1st plug was set at 500' with 50 sacks cement
- 2nd plug was set at 210' with 25 sacks cement
- 3rd plug was set at 40' with 10 sacks cement

RECEIVED
STATE CORPORATION COMMISSION
JUL 13 1971
CONSERVATION DIVISION
Wichita, Kansas


(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Dreiling Oil, Inc.
Address Victoria, Kansas 67671

STATE OF KANSAS, COUNTY OF ELLIS, ss.

I, Leo F. Dreiling, Pres. of Drlg. Contr. (employer, contractor, or operator) of the above-described well, being first duly sworn, on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leo F. Dreiling
Leo F. Dreiling, Route #2, Victoria, Kansas 67671
(Address)

SUBSCRIBED AND SWORN to before me this 12th day of July, 19 71



Patty Dreiling
PATTY DREILING
Notary Public.

My commission expires January 13, 1975

K-165-20401-0000
DREILING OIL, INC.

Victoria, Kansas 67671

WELL LOG

Company	Dreiling Oil, Inc. Route #2 Victoria, Kansas 67671	Sec. 21	Twp. 16	Rng. 19	
Farm	Brown No. 1	Location	NW NW NW		
Total Depth	3860'	County	Rush		
Comm.	7-3-71	Comp.	7-10-71	Elevation:	2086' K. B.
Contractor	Dreiling Oil, Inc. Victoria, Kansas 67671			2083'	D. F.
				2081'	G. R.

Casing Record

230' - 8 5/8"

Cement Record

150 sacks cement

Production:

D & A

Figures Indicate Bottom of Formations

0'	80'	Surface Soil & Clay
80'	130'	Shale
130'	230'	Shale
230'	515'	Shale
515'	765'	Red Bed
765'	840'	Sand
840'	996'	Sand
996'	1331'	Red Bed
1331'	1370'	Anhydrite
1370'	1615'	Shale
1615'	1985'	Shale
1985'	2195'	Shale & Lime
2195'	2245'	Lime & Shale
2245'	2445'	Lime & Shale
2445'	2635'	Lime & Shale
2635'	2840'	Lime & Shale
2840'	3065'	Lime & Shale
3065'	3270'	Lime & Shale
3270'	3345'	Lime
3345'	3470'	Lime
3470'	3545'	Lime
3545'	3630'	Lime
3630'	3710'	Lime
3710'	3770'	Lime
3770'	3820'	Lime
3820'	3825'	Arbuckle
3825'	3837'	Arbuckle
3837'	3842'	Lime
3842'	3860'	Lime
3860'	R.T.D.	

RECEIVED
 STATE CORPORATION COMMISSION
 JUL 13 1971
 CONSERVATION DIVISION
 Wichita, Kansas


STATE OF KANSAS)
)ss
 COUNTY OF ELLIS)

I, Leo F. Dreiling, of Dreiling Oil, Inc., upon oath states that the above and foregoing is a true and correct copy from the Daily Drilling Report from the Brown #1.

Leo F. Dreiling

 LEO F. DREILING

Subscribed and sworn to before me this 12th day of July, 1971.



Patty Dreiling

 PATTY DREILING NOTARY PUBLIC

My commission expires: January 13, 1975