


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Rush County. Sec. 27 Twp. 16 Rge. 19 NE/W
Location as "NE/CNW 1/4 SW 1/4" or footage from lines E/2 E/2 SW
Lease Owner F & M Oil Co., Inc.
Lease Name Graham Well No. 1
Office Address Box 505 Union Center, Wichita, Ks. 67202
Character of Well (Completed as Oil, Gas or Dry Hole) Dry Hole
Date Well completed 4-7-77 19 77
Application for plugging filed 4-7-77 19 77
Application for plugging approved 4-7 19 77
Plugging commenced 4-7- 19 77
Plugging completed 4-7- 19 77
Reason for abandonment of well or producing formation _____



Locate well correctly on above
Section Plot

If a producing well is abandoned, date of last production 19 _____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes
Name of Conservation Agent who supervised plugging of this well Leo Massey
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3750
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Well hole full of heavy mud.
Bottom plug @ 450' with 50 sks. 50/50 pozmix, 2% Get thru drill pipe
Mud to 240' - plug with 25 sacks cement thru drill pipe
At 40' 1/2 sack hulls, plug & 10 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
APR 12 1977

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Duke Drilling Co. Box 823 - Great Bend, Ks. 67530

STATE OF Kansas COUNTY OF Barton, ss.
Larry Curtis (employee of owner) or (~~owner or operator~~)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Larry Curtis
P.O. Box 823 - Great Bend, Ks. 67530
(Address)

SUBSCRIBED AND SWORN TO before me this 8th day of April, 19 77

Aleardy M. Hague
Notary Public.

My commission expires April 11, 1978

DRILLERS' WELL LOG

DATE COMMENCED: March 31, 1977
 DATE COMPLETED: April 7, 1977

F & M Oil Co.
 "GRAHAM # 1"
 E/2 E/2 SW
 Sec 27-T16-R19
 Rush County, Kansas

ELEVATION: 2032 K.B.

0 - 70'	Clay, Post Rock
70 - 913'	Shale, Sand
913 - 1245'	Red Bed
1245 - 1280'	Anhydrite
1280 - 3325'	Shale and Lime
3325 - 3329'	Shale
3329 - 3369'	Lime and Shale
3369 - 3623'	Lime
3623 - 3720'	Lime, Shale, Chert
3720 - 3750'	Sand
3750'	RTD

FORMATION DATA

Anhydrite	1245
Heebner	3325
Toronto	3345
Lansing	3369
Base K.C.	3628
Marmaton	3680
Reagon	3720
RTD	3750

SURFACE PIPE: Set used 6 5/8",
 28# pipe at 257' w/165 sacks
 Common, 2% Gel, 3% cc.

A F F I D A V I T

STATE OF KANSAS }
 COUNTY OF BARTON } ss.

Larry Curtis, of lawful age, does swear and state that the facts and statements herein contained are true and correct to the best of his knowledge.

Larry Curtis

Subscribed and sworn to before me this 11th day of April, 1977.

Kathleen M. Hague
 Notary Public

My Commission Expires: April 11, 1978

STATE OF KANSAS
 APR 12 1977
 Notary Public