

15-165-21102-0000  
STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Bldg.  
Wichita, Kansas 67202

Form CP-4  
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

COUNTY Rush SEC. 18 TWP. 16S RGE. 19 E/W  
Location as in quarters or footage from lines:  
SE SE NW


Locate Well  
correctly on above  
Section Platt.

Lease Owner High Plains Oil Explorations, Inc.  
Lease Name Oelkers Well No. 1  
Office Address 8575 West 110th St., Suite 105, Overland Park, KS  
Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole  
Date Well Completed 6-29-83  
Application for plugging filed 6-29-83  
Plugging commenced 6-29-83  
Plugging completed 6-29-83  
Reason for abandonment of well or producing formation Dry Hole

Was permission obtained from the Conservation Division or it's  
Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well J. H. Metz  
Producing formation                      Depth to top              bottom              T.D. 3970'  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	448'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud  
fluid was placed and the method or methods used in introducing it into the hold. If cement  
or other plugs were used, state the character of same and depth placed, from              feet  
to              feet for each plug set.

Mud laden fluid @ 3970' - 1400'  
60 sks cement @ 1400'  
50 sks cement @ 500'  
10 sks cement @ 40'  
10 sks cement in rathole  
10 sks cement in mousehole.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Emphasis Oil Operations

STATE OF KANSAS COUNTY OF RUSSELL, ss.  
Joe K. Branum (employee of owner) or (owner or operator) of the  
above-described well, being first duly sworn on oath, says: That I have knowledge of the  
facts, statements, and matters herein contained and the log of the above-described well as  
filed and that the same are true and correct. So help me God.

(Signature) Joe K. Branum  
P. O. Box 506, Russell, KS 67665-0506  
(Address)

SUBSCRIBED AND SWORN TO before me this 1st day of July, 19 83



RECEIVED  
STATE CORPORATION COMMISSION  
Glenda R. Tiffin, Notary Public.

My Commission expires: February 6, 1984

JUL 05 1983

CONSERVATION DIVISION  
Wichita, Kansas

15.165-21102-0000

EMPHASIS OIL OPERATIONS

P. O. Box 506

Russell, Kansas 67665-0506

DRILLERS LOG

OPERATOR: High Plains Oil Explorations, Inc.  
8575 West 110th St., Suite 105  
Overland Park, Kansas 66210

CONTRACTOR: Emphasis Oil Operations  
P. O. Box 506  
Russell, Kansas 67665-0506

LEASE: Oelkers WELL: #1

LOCATION: SE SE NW  
Section 18-16S-19W  
Rush County, Kansas

Total Depth: 3970'

Elevation: 2134' K.B.

Commenced: 6-20-83

Date Completed: 6-29-83

Casing: 8-5/8" @ 448' with 275 sks cement

Status: Dry Hole

DEPTHS & FORMATIONS

(All measurements from K.B.)

Top Soil & Sand	30'	Shale	3115'
Shale	1383'	Shale & Lime	3870'
Anhydrite	1417'	Lime (R.T.D.)	3970'

STATE OF KANSAS )  
                          ) ss:  
COUNTY OF RUSSELL)


Joe K. Branum, of Emphasis Oil Operations, states that the above and foregoing is a true and correct log of the above captioned well, to the best of his knowledge.

  
Joe K. Branum

Subscribed and sworn to before me this 1st day of July, 1983.

My Commission Expires: February 6, 1984.



  
Notary Public

RECEIVED  
STATE CORPORATION COMMISSION

JUL 05 1983

CONSERVATION DIVISION  
Wichita, Kansas