

15.135 30258-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Ness County, Sec. 30 Twp. 20 Rge. (E)25 (W)

Location as "NE/CNW/SW" or footage from lines NW NW

Lease Owner Mull Drilling Company, Inc.

Lease Name Slagle Well No. 1

Office Address 1625 Wichita Plaza Bldg., Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 8-6 19 66

Application for plugging filed 8-6 19 66

Application for plugging approved 8-6 19 66


Plugging commenced 8-6 19 66

Plugging completed 8-6 19 66

Reason for abandonment of well or producing formation no oil or gas found in commercial quantities

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Leo Massey, Hays, Kansas

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4476 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	244.36'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Pushed plug to 660'. Spotted with 25 sacks cement. Mudded back to 240', set plug and spotted with 25 sacks. Mud back to 40' and set solid bridge and capped with 10 sacks. 2 sacks in rat hole.

RECEIVED
STATE CORPORATION COMMISSION

AUG 18 1966

CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Rains & Williamson Oil Co.,

Address 1425 Wichita Plaza Bldg., Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

Lloyd R. Williamson, Partner (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct.

So help me God.

(Signature) Lloyd R. Williamson

Lloyd R. Williamson
1425 Wichita Plaza Bldg., Wichita, Kansas

(Address)

SUBSCRIBED AND SWORN to before me this 11th day of August, 19 66

Mary J. Brown
Mary J. Brown
Notary Public.

My commission expires 3-3-70

15-135-30258-0000

ROTARY DRILLING LOG

OPERATOR: Mull Drilling Company, Inc.
#1 Slagle
NW NW Section 30-20S-25W
Ness County, Kansas

CONTRACTOR: Rains & Williamson Oil Co.
COMMENCED: 7-25-66
COMPLETED: 8-6-66
REMARKS: Set 244.36' of 8-5/8" surface pipe with 175 sacks cement.

FORMATIONS

Soil Clay, Shale	75°
Shale	1130°
Sand	1342°
Shale & Red Bed	1650°
Anhydrite	1691°
Shale	2272°
Lime & Shale	3045°
Shale & Lime	3295°
Shale	3745°
Shale & Chalk	3761°
Shale & Lime	3900°
Lime & Shale	4075°
Lime	4200°
Lime & Shale	4246°
Lime	4407°
Lime & Chert	4432°
Lime	4476°
Rotary Total Depth (D&A)	4476°

RECEIVED
STATE CORPORATION COMMISSION

AUG 18 1966

CONSERVATION DIVISION
WICHITA, KANSAS

We certify the above log is true and correct to the best of our knowledge and belief.

RAINS & WILLIAMSON OIL CO.

Lloyd R. Williamson

Lloyd R. Williamson, Partner

Subscribed and sworn to before me, a Notary Public in and for the State of Kansas, County of Sedgwick, this 11th day of August, 1966.

My Commission Expires:
3-3-70

Mary J. Brown
Mary J. Brown Notary Public