

1 070196

15-135-21168-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Completed 3-76
C E/2 SW NE, SEC. 11, T 20 S, R 23 W

TECHNICIAN'S PLUGGING REPORT

Operator License # 6033

Operator: Murfin Drilling Company
Name & Address 250 North Water, Suite 300
Wichita, KS 67202

3300 feet from S section line
1650 feet from E section line

Lease Name Foos "F" Well # 2

County Ness 144.30

Well Total Depth 4440 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 445

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Murfin Drilling Company License Number 6033

Address 250 North Water, Suite 300, Wichita, KS 67202

Company to plug at: Hour: 2:00 pm Day: 18 Month: June Year: 19 86

Plugging proposal received from Ed Lofland

(company name) Murfin (phone) 316-267-3241

were: 4 1/2" at 4435' Perfs at 4354-58'

1st plug establish injection rate and pump 1 sack hulls and 25 sx cement (60/40 Pozmix

6% gel 3% cc) Displace with 4 1/2" wiper plug to 4150'. Perforate 2 spf at 900'.

Pump 175 sx cement (60/40 Pozmix 6% gel) (don't displace from casing). If cement does

not circulate pump 100 sx cement down annulus

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 5:00 pm Day: 18 Month: June Year: 19 86

ACTUAL PLUGGING REPORT 1st plug pumped 1 sack hulls and 25 sx cement (60/40 Pozmix 6% gel

3% cc) to bottom. 2nd plug displaced with 4 1/2" wiper plug to 4150'. Perforated 2 spf

at 900'. Pumped 175 sx cement (60/40 Pozmix 6% gel). Maximum pressure 1800 psi.

Pumped 100 sx cement down annulus. Maximum pressure 1000 psi and shut in 50 psi

SFL approximately 3000'

STATE CORPORATION COMMISSION

JUN 23 1986

Remarks: No recovery. Cemented by Halliburton.

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this form.)

INVOICED 6-18 14178 6-18
Please observe this plugging.

Signed Dan Jordan
(TECHNICIAN)

DATE JUN 23 1986

INV. NO. 14178