

State of Kansas



15-101-20065-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)RECEIVED
STATE CORPORATION COMMISSION
SEP 19 1974
CONSERVATION DIVISION
Wichita, KansasJ. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Darrell Kelso of Kelso Casing Pulling has this
date requested permission to plug the following described well:Mr. Kelso guarantees payment of the plugging fee.Operator's full Name: Hinkle Oil Company,Complete Address: 1016 Union Denter, Wichita, Kansas.Lease Name: Dickey Well No. 1Location: NW-SE-NE Sec. 25 Twp. 16 Rge. (E)(W) 30County: Lane Total Depth 4590' Oil Well XGas Well Input Well SWD Well D & A Lost Hole Mr. Kelso was instructed to plug the well as follows:290'--8 5/8" Surface casing, cement circulated with 180 Sx.4559'--5 1/2" Production casing cemented on bottom with 275 Sx.. Well
Plugged back to 4525' with Top of perforations @ 4437'.Push plug to 4400', sand back to 4350' and set 5 Sx. cement with dump
bailer. Pull 5 1/2" casing and squeeze well with 5 sacks hulls, 30 sacks
gel and 150 Cu. Ft. cement, staged.

Very truly yours,

Conservation Division Agent