

State of Kansas



ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg.

WICHITA, KANSAS 67202

RECEIVED
 STATE CORPORATION COMMISSION
 NOV 21 1968
 CONSERVATION DIVISION
 Wichita, Kansas

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

November 16, 1968

J. Lewis Brock
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Herb. Mason of Dunne-Gardner Drlg. Co., Inc. has this date requested permission to plug the following described well:

Mr. Mason guarantees payment of the plugging fee.

Operator's full Name: Jayhawk Oil Company

Complete Address: 103 One-Twenty Bldg., Wichita, Kansas 67202

Lease Name: Gross Well No. 1

Location: C NW NE Sec. 30 Twp. 21 Rge. 7 ~~(E)~~ (W) X

County: Rice Total Depth 3925' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Mason was instructed to plug the well as follows:

Fill hole with heavy mud. Pump 50 sacks cement through drill pipe at

600'. Pump 20 sacks cement through drill pipe at 155'. Push plug and

1/2 sack hulls to 40' and cap hole with 10 sacks cement.

Bridge rathole and cement with 2 sacks.

Very truly yours,

W. L. Loman
 Conservation Division Agent