



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
245 North Water
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
245 North Water
Wichita, Kansas 67202

Dear Sir:

Mr. Curtis of Duke Drlg. has this date requested permission to plug the following described well:

Mr. Curtis guarantees payment of the plugging fee.

Operator's full Name: F & M Oil Co., Inc.

Complete Address: 505 Union Center, Wichita, Ks.

Lease Name: Graham Well No. 1

Location: E/2 E/2 SW Sec. 27 Twp. 16 Rge. (E)(W) 19

County: Rush Total Depth 3750' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Curtis was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set 50 sk cmt plug at 450' thru drill

pipe. Heavy mud to 240' set 25 sk cmt plug thru drill pipe. Heavy

mud to 40' set solid bridge & 10 sk cmt plug to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION

APR 08 1977

Very truly yours,
CONSERVATION DIVISION
Wichita, Kansas

Geo. Massey
Conservation Division Agent