



JOHN CARLIN
R. C. LOUX
JANE T. ROY
WILLIAM G. GRAY

Governor
Chairman
Commissioner
Commissioner

Carol J. Larson, Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
245 North Water
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
245 North Water
Wichita, Kansas 67202

Dear Sir:

Mr. Darrell Stephens, Abercrombie Drilling Inc. has this date requested permission to plug the following described well

Mr. Stephens guarantees payment of the plugging fees

Operator's full Name: F. & M. Oil Co.

Complete Address: 422 Union Center - Wichita, Mo. 67202

Lease Name: Little Well No. # 1 - "A"

Location: NW-NW-NW Sec 23 Twp. 16 Rge. 19 (E)(W)

County: PUSH Total Depth 3680 Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Stephens was instructed to plug the well as follows:

- 8 5/8" 322 FE SP. CUC. w/ 200^{SE} Cement 2% Gel - 3% CaCl.
- Ordered 105^{SE} 50/50 Permian 4% Gel + 8 5/8" Plug (Elev 2053)
- 1st Plug @ 660 FE w/ 60^{SE} cement
- 2nd Plug @ 300 FE w/ 30^{SE} cement
- 3rd Plug - solid bridge shells Plug @ 40 FE to 0 w/ 10^{SE} cement
- 5th In Rat Hole

Very truly yours, By Sam Cmt.

Marion Schmidt
Conservation Division Agent

RECEIVED
STATE CORPORATION COMMISSION
MAY 5 1960
CONSERVATION DIVISION
WICHITA, KANSAS