

State of Kansas



15.165-20045-0000

FORM - CP-2  
Rev. 9-8-64

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

## State Corporation Commission

### CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

#### VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

AUG 1 1967

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Wynn of Gabbert-Jones, Inc., has this  
date requested permission to plug the following described well:

Mr. Wynn guarantees payment of the plugging fee.

Operator's full Name: Nadel-Gussman

Complete Address: 625 Union Center Wichita, Kansas

Lease Name: Dechant Well No. 1

Location: NW NE SE Sec. 13 Twp. 16 Rge. 19 (E)(W) X

County Rush Total Depth 3708 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Wynn was instructed to plug the well as follows:

Gum pits, circulate heavy mud, set 25 sc cement plug W/ 4 % cc at 600'.

Displace 65 sc cement from top of plug. Heavy mud to 220' set cementing

plug and displace 20 sc cement. Heavy mud to 40' set cementing plug, 1/2

sc hulls and 10 sc cement to base of cellar. Plug rat hole with 2 sc cem.

Very truly yours,

Leo F. Massey  
Conservation Division Agent