

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

WM. H. AYER Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

AUG 9 1966

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Walker of Rains & Williamson Drlg. Co. has this date requested permission to plug the following described well:

Mr. Walker guarantees payment of the plugging fee.

Operator's full Name: Mull Drilling Company Inc.

Complete Address: 1625 Wichita Plaza Wichita, Kansas

Lease Name: Slagle Well No. 1

Location: C NW NW Sec. 30 Twp. 20 Rge. 25 (E)(W) X

County Ness Total Depth 4476 Oil Well     

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Walker was instructed to plug the well as follows:

Gun pits, Circulate heavy mud, set cementing plug at 660 Ft.  
and displace 25 sc cement thru drill pipe. Heavy mud to 240 Ft. set  
cementing plug and displace 25 sc cement thru drill pipe. Heavy mud  
to 40 Ft. set cementing plug, 1/3 sc hulls and 10 sc cement to base  
of celler. Plug raj hole with 2 sc cement.

Very truly yours,

[Signature]  
Conservation Division Agent