

15-1165-19011-0000

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

API NUMBER 11-16-62

LEASE NAME HONDERICK

WELL NUMBER #1

2310 Ft. from S Section Line

2970 Ft. from E Section Line

SEC. 6 TWP. 17S RGE. 16 (E) or (W)

COUNTY RUSH

Date Well Completed 11-16-62

Plugging Commenced 2-24-97

Plugging Completed 2-24-97

LEASE OPERATOR AFG Energy Inc.

ADDRESS P.O. Box 458; Hays, KS 67601

PHONE: (913) 625-6374 OPERATORS LICENSE NO. 3456

Character of Well GAS

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 2-24-97 (date)

by RICHARD LACEY (KCC District Agent's Name).

Is ACO-1 filed? YES If not, Is well log attached?

Producing Formation ARBUCKLE Depth to Top 3596 Bottom 3602 T.D. 3602

Show depth and thickness of all water, oil and gas formations. P.B.T.D. 3520'

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
<u>ARBUCKLE</u>	<u>GAS & WATER</u>	<u>3596</u>	<u>3602</u>	<u>8 3/8</u>	<u>212</u>	<u>NONE</u>
<u>TOPEKA</u>	<u>GAS & WATER</u>	<u>3603</u>	<u>3650</u>	<u>4 1/2</u>	<u>3596</u>	<u>NONE</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set
RUN TUBING TO 3000' MIXED 125 SXS 60/40 PZ 10% GEL, 300# HULLS,
PULL TUBING TO 1200' MIXED 75 SXS 60/40 PZ 10% GEL, 200# HULLS,
Cement circulated, Dumped 15 SXS DOWN 4 1/2 CS 60/40 PZ, 10% GEL

Name of Plugging Contractor Allied Cementing Co. Inc. License No.

Address Russell, KS 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: AFG Energy Inc.


STATE OF Kansas COUNTY OF Ellis, ss.

Edgar L. Glassman

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the same are true and correct, so help me God.

(Signature) Edgar L. Glassman

(Address) P.O. Box 458; Hays, KS 67601



SUBSCRIBED AND SWORN TO before me this 14th day of March, 19 97

Linda K. Pfannenstiel
Notary Public

My Commission Expires: 2/15/2000

USE ONLY ONE SIDE OF EACH FORM