

API NUMBER 15-165-20,655-0000

LEASE NAME Erbes "A"

WELL NUMBER #1

2310 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 1 TWP. 17S RGE. 17 (E) or (W)

COUNTY Rush

Date Well Completed 11-10-77

Plugging Commenced 3-10-94

Plugging Completed 3-10-94

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR AFG Energy Inc.

ADDRESS P.O. Box 458 Hays, Ks. 67601-0458

PHONE#(913) 625-6374 OPERATORS LICENSE NO. 03456

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 3-09-94 (date)

by Mr. Lacy (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? \_\_\_\_\_

Producing Formation Topeka Depth to Top 3062' Bottom 3068' T.O. 3180'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Topeka	Gas & water	3062	3068	8 5/8"	258	None
				4 1/2"	3619	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set. The well had a Dakota Leak. Ran tubing in to 3006". Mixed 50 sxs. 60/40 Poz., 6% gel & 200# hulls. Pulled tubing to 1260'. Circulated hole full with 60/40 Poz., 6% gel. Circulated. Culled tubing out of hole. Hooked to 8 5/8" Casing. Mixed 20 sxs. of same with 50# hulls and circulated up 4 1/2" Casing. Mixed another 50# of hulls and 105 sxs. of same cement. 50# on casing.

Name of Plugging Contractor Allied Cementing License No. \_\_\_\_\_

Address Russell, Kansas

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: AFG Energy Inc.


STATE OF Kansas COUNTY OF Ellis, ss.

Henry W. Piesker (Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) Henry W. Piesker

(Address) P.O. Box 458 Hays, Ks. 67601-0458



SUBSCRIBED AND SWORN TO before me this 14th day of March, 19 94

Linda K. Pfannenstiel  
 Notary Public

My Commission Expires: 2/5/96

USE ONLY ONE SIDE OF EACH FORM

RECEIVED  
 STATE CORPORATION COMMISSION  
 MAR 15 1994

CONSERVATION DIVISION  
 Wichita, Kansas