


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Ness County. Sec. 35 Twp. 20S Rge. 25W E/W  
Location as "NE/CNW 1/4 SW 1/4" or footage from lines \_\_\_\_\_

\_\_\_\_\_ C-SW NE  
Lease Owner The National Oil Company  
Lease Name Amstutz Well No. 1  
Office Address 200 W. Douglas-Suite 550, Wichita, KS  
Character of Well (Completed as Oil, Gas or Dry Hole) 67202  
Dry Hole



Locate well correctly on above  
Section Plat

Date Well completed March 3, 1980  
Application for plugging filed verbal Application 19\_\_\_\_  
Application for plugging approved Verbal Approval 19\_\_\_\_  
Plugging commenced March 3, 1980  
Plugging completed March 3, 1980  
Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Marion Schmidt  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4,466'  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	573'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with heavy rotary mud from 4,466 ft. (rotary total depth) to 820 ft. Set plug at 820 ft. and cemented with 70 sacks cement. Filled hole with heavy rotary mud from 820 ft. to 480 ft. Set plug at 480 ft. and cemented with 20 sacks cement. Filled hole with heavy rotary mud from 480 ft. to 40 ft. Set solid plug at 40 ft. and cemented to cellar with 10 sacks cement, 5 sacks cement in rat hole.

Plugging operations accomplished utilizing Halliburton Oil Well cementing pump truck through 4 1/2 inch drill pipe.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Halliburton Services  
410 Union Center Bldg., Wichita, Kansas

RECEIVED  
STATE CORPORATION COMMISSION  
WICHITA, KANSAS  
MAR 4 1980

STATE OF Kansas COUNTY OF Sedgwick  
Dean Britting, Agent (Agent of owner) ~~XXXXXX~~ (owner or operator) ~~XXXXXXXXXX~~

of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dean Britting  
200 N. Main, Wichita, Kansas 67202  
(Address)

SUBSCRIBED AND SWORN TO before me this 3rd day of March, 1980

Elsie Willison  
Elsie Willison - Notary Public.

My commission expires July 25, 1982

KANSAS DRILLERS LOG

COMPANY The National Oil Company  
FARM Amstutz NO. 1

SEC. 35 T. 20S. 25W  
LOC. C-SW NE

COUNTY Ness

ROTARY TOTAL DEPTH 4,466'  
COMM. February 12, 1980 COMP. February 21, 1980  
CONTRACTOR H-30, INC. (Rig #2)  
ISSUED March 3, 1980

CASING

10 3/4"  
8 5/8" Set at 573' cemented w/350 exs cement  
5 1/2"  
4 1/2"

ELEVATION 2,370' K.B.

FIGURES INDICATE BOTTOM OF FORMATIONS

Shale	578'
Shale and Shells	1,080'
Sand	1,300'
Shale and Red Bed	1,370'
Shale and Sand	1,540'
Red Bed	1,642'
Anhydrite	1,678'
Red Bed and Sand	1,925'
Shale and Lime	2,765'
Lime and Shale	4,085'
Lime	4,466'
Rotary Total Depth	4,466'

I hereby certify the above and foregoing to be a true and correct log of the above described well as shown by the drilling reports.

H-30, INC.

*Dean Britton*  
Dean Britton

State of Kansas )  
                          ) SS:  
County of Sedgwick )

Subscribed and Sworn to before me a Notary Public in and for said county and state this 3rd day of March, 1980.

*Elsie Willison*  
Elsie Willison - Notary Public

My Commission Expires:  
July 25, 1982

RECEIVED  
STATE CORPORATION COMMISSION  
MAR - 4 1980  
CONSERVATION DIVISION  
Wichita, Kansas