

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-135-23,542-0000

LEASE NAME Almquist BK

WELL NUMBER 1

1980 Ft. from S Section Line

4290 Ft. from E Section Line

SEC. 35 TWP. 20 RGE. 25 (E) or (W)

COUNTY Ness

Date Well Completed 1-6-91

Plugging Commenced 1-6-91

Plugging Completed 1-6-91

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Vess Oil Corporation

ADDRESS 8100 E. 22nd St. N., Bldg. 300 Wichita, KS 67226

PHONE# (316), 682-1537 OPERATORS LICENSE NO. 5030

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 1-3-91 (date)

by Case Morris (KCC District Agent's Name).

Is ACO-1 filed? to be filed If not, is well log attached? yes
by operator

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4490

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

Bottom Plug: @ 1725' w/50 sacks cement thru drill pipe

Next Plug: @ 900' w/50 " " " " " " 15 sacks in Rat Hole

Next Plug: @ 475' w/50 " " " " " "

Top Plug: @ 40' w/10 " " " " " "

(if additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Duke Drilling Co., Inc. License No. 5929

Address P.O. Box 823 Great Bend, KS 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Vess Oil Corporation

STATE OF Kansas COUNTY OF Barton, ss.

Jay Schneider (Employee of Operator) or ~~XXXXXXXXXX~~
 above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) Jay Schneider

(Address) P.O. Box 823 Great Bend, KS 67530

SUBSCRIBED AND SWORN TO before me this 8th day of January, 19 91

Paula Ann Landrum
 Notary Public

My Commission Expires: _____



DRILLER'S WELL LOG

DATE COMMENCED: December 27, 1990
DATE COMPLETED: January 6, 1991

Vess Oil Corporation
ALMQUIST 'BK' #1
C E/2 NW 5W
Sec. 35, T20S, R25W
Ness County, Ks.

0 - 1987' Surface Soil, Clay, Shale
1987 - 3788' Lime & Shale
3788 - 3808' Shale & Lime
3808 - 4180' Lime
4180 - 4207' Shale & Lime
4207 - 4360' Lime, Shale, Chert
4360 - 4380' Lime
4380 - 4453' Sand
4453 - 4490' Chert & Lime
4490' RTD


ELEVATION: 2404 K.B.

Surface Pipe: Set used
8-5/8", 287 pipe @ 754'
w/275 sacks 60/40 pozmix
2% gel 3% ca.



AFFIDAVIT

STATE OF KANSAS
COUNTY OF BARTON) ss

Jay Schneider of lawful age, does swear and state that the facts and statements herein are true and correct to the best of his knowledge.



Subscribed and sworn to before me this 8th day of January 1990.


Notary Public

CONSULT THE DIVISION
Wichita, Kansas