

15-165-81824-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

OR
FORMATION PLUGGING RECORD

Strike out upper line
when reporting plug-
ging off formations.

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Rush County, Sec. 29 Twp. 17S. Rge. (E) 16 (W)

Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SW SW NW

Lease Owner Westgate-Greenland Oil Company

Lease Name Hartung Well No. 1

Office Address 1022 Union National Bank Building, Wichita 2, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) dry hole

Date well completed August 3, 1948 19

Application for plugging filed August 3, 1948 19

Application for plugging approved August 3, 1948 19

Plugging commenced August 3, 1948 19

Plugging completed August 3, 1948 19

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? yes

Name of Conservation Agent who supervised plugging of this well C. D. Stough

Producing formation Depth to top Bottom Total Depth of Well Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Surface		0	970	8 5/8"	970	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud from 3584 to 965 feet
Dumped in 50 sacks cement and filled with heavy mud to 15 feet.
Dumped in 5 sacks cement and filled hole to cellar top.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to G. E. Bitler, c/o Westgate-Greenland Oil Company
Address 1022 Union National Bank Building, Wichita 2, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, SS.
G. E. Bitler (employee of owner) or (owner or operator)

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) G. E. Bitler


1022 Union National Bank Building, Wichita 2, Ks
(Address)

SUBSCRIBED AND SWORN TO before me this 7th day of August, 19 48

Ester Russell

Notary Public.

My commission expires May 25, 1949



15-165-01824-0000

COMPANY: Westgate-Greenland Oil Company
 CONTRACTOR: Mallard Drilling Company
 FARM: Hartung #1
 LOCATION: SW Corner NW/4
 Sec. 29-17S-16W Rush County, Kansas
 COMMENCED: July 22, 1948
 COMPLETED: August 3, 1948--Rotary

0	to	100	Surface sand
100	to	470	Shale and shells
470	to	525	Shale
525	to	650	Sand
650	to	830	Shale and shells
830	to	1124	Shale and shells
1124	to	1200	Anhydrite
1200	to	1420	Shale and shells
1420	to	1510	Shale and shells
1510	to	1700	Salt and shale
1700	to	1815	Shale and shells
1815	to	2000	Lime and sand
2000	to	3075	Lime and shale
3075	to	3563	Lime
3563	to	3584	Granite
		3584	T.D. Rotary

Set 970 feet of 8 5/8" surface pipe. 28#. Cemented with 385 sacks cement.

TOP; Granite--3563

DRY, ABANDONED AND PLUGGED

CERTIFICATE

I, C. C. Nelson, do hereby certify that the above and foregoing is a true and correct copy of log of the Hartung #1, Section 29-17S-16W, Rush County, Kansas as reflected by files of the Mallard Drilling Company.

C. C. Nelson

Subscribed and sworn to before me a Notary Public, within and for Sedgwick County, Kansas, this 5th day of August 1948.

Lawrence Wright

My commission expires 12/4/48.

