


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202



Locate well correctly on above
Section Plat

Rush County. Sec. 1 Twp. 17 Rge. 17 ~~EX~~
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
SW/SW/NE

Lease Owner Frontier Oil Company
Lease Name Kaiser "A" Well No. 1
Office Address 1437 N. Franklin, Russell, KS 67665
Character of Well (Completed as Oil, Gas or Dry Hole)

Oil
Date Well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 8/30 1978
Plugging completed 9/7 1978
Reason for abandonment of well or producing formation

Depleted
If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey
Producing formation Depth to top Bottom Total Depth of Well 3666'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	213'	None
				4 1/2"	3230'	2553.15'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from feet to
feet for each plug set.

Dumped sand to 3000' and four (4) sacks cement
Shot pipe at 2600'
Spotted oil behind casing
Pulled 79 joints of 4 1/2" plastic-wrap casing
Plugged well with two (2) sacks hulls, twenty sacks gel, 120 sacks 50/50 pozmix with 6% added
gel

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Rockhold Engineering, Inc.

STATE OF Kansas COUNTY OF Barton, ss.
James W. Rockhold (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.

(Signature) James W. Rockhold
James W. Rockhold Box 698 Gt. Bend, KS 67530
(Address)

SUBSCRIBED AND SWORN TO before me this 13th day of September, 1978

STATE NOTARY PUBLIC
CATHY L. COLE
Barton County, Kansas
My Appt. Exp. June 14, 1982

My commission expires

RECEIVED
STATE CORPORATION COMMISSION

SEP 15 1978

CONSERVATION DIVISION
Wichita, Kansas

DRILLERS LOG

Kaiser "A" No. 1

CASING RECORD: COMPANY: Frontier Oil Company DESCRIPTION: SW SW NE
 8 5/8" @ 213' CONTRACTOR: Red Tiger Drilling Co. 1-17S-17W
 w/135 sx cement RUSH CO., Kansas
 COMMENCED: November 26, 1962 ELEVATION: 2044 DE
 4 1/2" @ 3230' w/150 sx cement COMPLETED: December 5, 1962 2046 RE
 TOTAL DEPTH:
 3666'

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface	0	213	
Shale	213	448	
Sand	448	775	
Shale	775	1165	
Anhydrite	1165	1205	
Shale & Shells	1205	1300	
Shale & Red Bed	1300	1810	
Shale	1810	1900	
Shale & Lime	1900	2880	
Lime	2880	3666	

I certify that this is a true and correct copy of the above log to the best of my knowledge.

FRONTIER OIL COMPANY

George A. Angle
 George A. Angle

Subscribed and sworn to before me this 11th day of December, 1962.

Minnie V. Head
 Notary Public

My Commission Expires:

11-17-66

RECEIVED
 STATE COMMISSION
 JUL 14 1978
 7-14-78
 DIVISION
 Wichita, Kansas