

-01014-
15.135-0000

WELL PLUGGING RECORD

Give All Information Completely
Make Entries Accurate
Mail or Delivery Report to:
Conservation Division
State Corporation Commission
311 N. Broadway
Wichita, Kansas

Ness County, Sec. 34 Twp. 20S Rge. (E) 25 (W)

Location as "NE/CNWSW" or footage from lines C SW NE

Lease Owner Wilcox Oil Company

Lease Name Fehrenbach Well No. 1

Office Address Box 1440, Tulsa, Oklahoma

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed March 13 1964

Application for plugging filed March 13 1964

Application for plugging approved March 13 1964


Plugging commenced March 13 1964

Plugging completed March 13 1964

Reason for abandonment of well or producing formation No oil or gas found in commercial quantities.

If a producing well is abandoned, date of last production - - - 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plot

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas

Producing formation None Depth to top - Bottom - Total Depth of Well 4600 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	377'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Set plug At 540', Cemented through drill pipe with 20 sacks cement.
Second plug set at 370', Cemented through drill pipe with 20 sacks cement.
Filled hole with rotary mud to 40' of base of cellar, and capped with 12 sacks cement, 3 sacks cement in rathole.

RECEIVED
STATE CORPORATION COMMISSION

MAR 18 1964

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Rains & Williamson Oil Co.

Address 1425 Wichita Plaza Building, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.

Wilson Rains (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) Wilson Rains

Wilson Rains

1425 Wichita Plaza, Wichita, Kansas

(Address)

Subscribed AND SWORN to before me this 16th day of March 1964



Shirley Keck
Notary Public.

My commission expires January 8, 1968

ROTARY DRILLING LOG

Operator: Wilcox Oil Company
No. 1 FEHRENBACH
C SW NE Sec. 34-20S-25W
Ness County, Kansas

Contractor: Rains & Williamson Oil Co.
Commenced: 2-28-64
Completed: 3-13-64

Remarks: Set 8-5/8" surface casing
at 377' with 240 sacks cement.

Formations:

Surface Clay	40'
Shale	380'
Shale & Shells	450'
Shale	700'
Red Bed & Shale	993'
Anhydrite	1014'
Shale	1092'
D. Sand	1310'
Shale & Red Bed	1405'
Shale	1623'
Anhydrite	1636'
Shale	1810'
Shale & Shells	2000'
Shale & Lime	2365'
Lime & Shale	2780'
Shale & Lime	3780'
Lime & Shale	3980'
Lime	4185'
Lime & Shale	4250'
Lime	4300'
Lime & Shale	4405'
Lime & Chert	4457'
Lime	4480'
Lime & Shale	4535'
Lime & Chert	4575'
Lime	4600'
Rotary Total Depth	4600'

RECEIVED
STATE CORPORATION COMMISSION

MAR 18 1964

CONSERVATION DIVISION
Wichita, Kansas

We certify the above log is true
and correct to the best of our
knowledge and belief.

RAINS & WILLIAMSON OIL CO.

By Wilson Rains
Wilson Rains, Partner

Subscribed and sworn to before me, a Notary Public in and for the
State of Kansas, County of Sedgwick, this 16th day of March, 1964.

My Commission Expires:
January 8, 1968

Shirley Reck
Shirley Reck, Notary Public