

15-135-20166-0000

Form CP-3
Rev. 6-26-62

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUL 23 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name R. V. Lehner

Complete Address: P. O. Box 398 Ness City, Kansas

Lease Name Lehner Well No. B-1

Location C / SW SW Sec. 18 Twp. 20 Rge. 23 (E) (W) X

County Ness Total Depth 4410

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Strata Drlg.

Address: Wichita, Kansas License No.

Operation Completed: Hour 8:30 A Day 18 Month 7 Year 1968

The Above well was plugged as follows:

RTD 4410' 8 5/8 csg set at 288' cwc Cem Mat. 100 sc 50-50 poz cem. W/6% total gel.
Gunned pits, circulated heavy mud, set cementing plug at 720' and displaced 70 sc cem.
thru drill pipe. Heavy mud to 270' set cementing plug and displaced 20 sc cement thru
drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cement to base
of cellar. Plugged rat hole with 2 sc cement;

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 7/23/68
INV. NO. 8159-W

Signed: [Signature]
Well Plugging Supervisor