

15-135-19171-0000

Form CP-3
Rev. 6-26-62KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, KansasRECEIVED
STATE CORPORATION COMMISSION

NOV 3 1962

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Wilcox Oil Co

Complete Address: Box 1440 Tulsa, Okla

Lease Name Mc Ginnis Well No. 1

Location CSE SE Sec. 34 Twp. 20 Rge. (E) (W) 25

County Ness Total Depth 4550

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Comstock Pipe Pulling Co

Address: Stafford, Kans License No. 490

Operation Completed: Hour 12:30PM Day 5 Month 11 Year 62

The Above well was plugged as follows:

8 5/8" 398' circulated with cement - 5 1/2" 4550' with 150 sax cement -
perforated 4472'

Filled with sand to 4460', set 4 sax cement with dump bailer, pulled
3362' 5 1/2" to 600', circulated bolw with heavy gel mud through 5 1/2" at 600',
displaced 20 sax cement through 5 1/2" at 600', heavy mud to 200', displaced
20 sax cement through 5 1/2" - heavy mud to 35', set bridge and filled to
bottom cellar with cement.

Mudding and cementing by Sun Cementing Co.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Edson Lee
Well Plugging SupervisorDATE 11/8/62
INV. NO. 5988-W