

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
OCT 24 1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Frontier Oil Company

Complete Address 1720 Wichita Plaza, Wichita, Kansas 67202

Lease Name Brack "C" Well No. 1

Location NW SW NW Sec. 29 Twp. 17 Rge. (E) (W) 16

County Rush Total Depth 3580'

Abandoned Oil Well XX Gas Well ✓ Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Co. Tools by Allied Cementing Co.

Address License No.

Operation Completed: Hour 5 P Day 21 Month 10 Year 1974

The above well was plugged as follows:

Total Depth 3580' 8 5/8 csg set at 208' cwc 135 sk.

4 1/2 csg set at 3578' cw 275 sk.

No pipe recovered.

Pumped down annulus (8 5/8-4 1/2) with 70 sk 50-50 poz 6%.

pumped down 4 1/2 csg with 300 lbs hulls -25 sk gel & water -released 4 1/2 plug &

pumped 50 sk 50-50 poz 6% by Allied Cementing Co.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo F. Massey
Well Plugging Supervisor

DATE 10/24/74

INV. NO. 186-W