

2

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JAN 18 1979

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 135 - 21,555 - 0000 (of this well)

Operator's Full Name National Oil Co.

Complete Address 200 W Douglas Ste. 550 Wichita, Ks.

Lease Name Almquist Well No. 2

Location C SW NW Sec. 35 Twp. 20 Rge. (E) (W) 25

County Ness Total Depth 4520'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor H-30 Drlg.

Address Wichita, Ks. License No.

Operation Completed: Hour 6 P Day 16 Month 1 Year 1979

The above well was plugged as follows:

RTD 4520' 8 5/8 csg set 409' cwc Plg. Mat. 50-50 poz 6% total gel.

Gunned pits, circulated heavy mud, set 70 sk cmt plug at 550' thru drill pipe.

Heavy mud to 240' set 20 sk cmt plug thru drill pipe. Heavy mud to 40' set solid
bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Geo. Massey
Well Plugging Supervisor

DATE 1-19-79
INV. NO. 8980 W