

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-32-21, 392-0000

245 North Water
Wichita, KS 67202

Operator's Full Name NATIONAL OIL COMPANY

Complete Address 200 WEST DOUGLAS, #800 WICHITA, KANS. 67202

Lease Name ALMQUIST Well No. #1

Location C-NW-SW Sec 35 Twp. 20 Rge. 25 (East) (West)

County NESS Total Depth 4480 FE

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor ALLIED CEMENTING COMPANY, INC.

Address BOX 31-332 W. WICHITA, RUSSEL, KS. License No. _____

Operation Completed: Hour: 5:30 PM Day: 26 Month: JAN Year: 1981

The above well was plugged as follows:

8 5/8" 211 FE SP. CUM w/185 ST → 5 1/2" SET @ 4470 FE w/150 ST
PERFS 4452' TO 4460 FE → D.V. TOOL @ 1602 CNT CIRCULATED TO TOP.
NO PIPE RECOVERY.

ORDERED -135 ST 50/150 POLMIX 6% GEL → 26 ST GEL. → 3 ST HULL'S
AND 5 1/2" PLUG. → PUMPED IN WITH PUMP TRUCK.

PUMPED IN 5 1/2" → 2 ST HULL'S - 35 ST CNT → 26 ST GEL. → 1 ST HULL'S.
RELEASED PLUG. AND -100 ST CNT. MAX. PRESSURE - 400 LB

CEMENTED BY ALLIED CNT.

STAT. RECEIVED
DIVISION

JAN 23 1981

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Conservation Division Agent

DATE 2-18-80

INV. NO. 4512-44