

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION

FEB 27 1973

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Braden-Deem Inc.
Complete Address 200 E 1st, Wichita, Kansas
Lease Name G. Miller "B" Well No. 1
Location SW NE Sec. 12 Twp. 22 Rge. 23 ~~(E)~~ (W)
County Hodgeman Total Depth 4563'
Abandoned Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D & A _____
Other well as hereafter indicated _____
Plugging Contractor Knights Casing Pulling
Address Chase, Kansas License No. 624
Operation Completed: Hour 12:30 PM Day 20 Month 2 Year 1973

The above well was plugged as follows:

9 5/8" to 257' circulated w/ cement. 7" to 4555' cemented.
Open hole 4555' to 4563' Plug bottom w/ sand & 5 sacks cement
Top of cement 4500' Mud 4500' to 700'
Spotted 70 sacks cement 700' to 400' Mud 400' to 200'
Plug. & 50 sacks cement 200' to 0'. Allied Pump Truck
Pulled 1800' of 7" casing.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor

INVOICED
DATE 2/28/73
INV. NO. 9038-14