

STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

Rev. 03/92

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # 5007-22289000 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR Woolsey Petroleum Corp KCC LICENSE # 5506 ^{6/96}
(owner/company name) (operator's)

ADDRESS 107 N. Market CITY Wichita

STATE Kansas ZIP CODE 67202 CONTACT PHONE # (316) 267-4379

LEASE Donovan WELL# C-1 SEC. 10 T. 34 R. 13W (East/West)

SPOT LOCATION/0000 COUNTY Barber

1225 FEET (in exact footage) FROM S/N (circle one) LINE OF SECTION (NOT Lease Line)

670 FEET (in exact footage) FROM E/W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL D&A SWD/ENHR WELL DOCKET# _____

CONDUCTOR CASING SIZE 20" SET AT 65 CEMENTED WITH Redi-Mix (full) SACKS

SURFACE CASING SIZE 8 5/8" SET AT 392' CEMENTED WITH 200 SACKS

PRODUCTION CASING SIZE 4 1/2" SET AT 5098' CEMENTED WITH 200 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: See Attachment

ELEVATION 1822'/1831' T.D. 5100' PBDT 5089' ANHYDRITE DEPTH 1560'
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING 50' sand & 4 sax cement above perforation, cut & lay down casing. Pump 300# cotton seed hulls + 10 sax gel + 50 sax cement + 10 sax

gel+100# cotton seed hulls + 85/8" wiper plug + 100 sax cement. Use 60/40 poz
(If additional space is needed attach separate page) + 6% gel.

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? yes IS ACO-1 FILED? yes

If not explain why? _____

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Carl W. Durr PHONE# () 316-886-5606

ADDRESS P.O. Box 168 city/state Medicine Lodge, KS ^{JAN 11 1996} ⁰¹⁻⁰⁹⁻⁹⁶

PLUGGING CONTRACTOR Clarke Corp KCC LICENSE # 5105 ^{6/96}
(company name) (contractor's)

ADDRESS Medicine Lodge, KS PHONE # () 886-5665

PROPOSED DATE AND HOUR OF PLUGGING (If known?) 01/22/96 AM

PAYMENT OF THE PLUGGING FEE (K.S.A. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 1/3/96 AUTHORIZED OPERATOR/AGENT: Carl W. Durr
(signature)



Kansas Corporation Commission

Bill Graves, Governor Susan M. Seltsam, Chair F.S. Jack Alexander, Commissioner Timothy E. McKee, Commissioner
Judith McConnell, Executive Director

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

January 9, 1996

Woolsey Petroleum Corporation
107 N Market
Wichita KS 67202

Donovan C-1
API 15-007-22,289 *0000*
1225 FNL 670 FWL
Sec. 10-34S-13W
Barber County

Dear Carl W. Durr,

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

David P. Williams
David P. Williams
Production Supervisor

District: #1
304 W. McArtor
Dodge City, KS 67801
(316) 225-6760

WOOLSEY PETROLEUM CORPORATION

107 North Market - Suite 600 - Wichita, Kansas 67202-1807

Donovan C-1
Sec. 10-34S-13W
Barber County, Kansas

15-007-22289-0000

WELL PLUGGING APPLICATION FORM ATTACHMENT

PERFORATIONS AND BRIDGEPLUG SETS AS FOLLOWS:

5013' - 5012' - 5006'

4993' to 5001', 4983' to 4987', 4914' to 4932'

CIBP @ 4850'

4132' to 4144'

RECEIVED
STATE CORPORATION COMMISSION

JAN 13 1996

ML *eq*

15-007-22289-0000



MICRORESISTIVITY LOG

LOCATION 670' FWL. 1225' FNL PROVINC/CO. BARBER FIELD AETNA WELL DONOVAN "C" #1 COMPANY TXO PRODUCTION CORPORATION	COMPANY TXO PRODUCTION CORPORATION WELL DONOVAN "C" #1 FIELD AETNA PROVINCE/COUNTY BARBER COUNTRY/STATE U.S.A. / KANSAS PERMIT NUMBER 007-22289
	LOCATION 670' FWL. 1225' FNL LSD SEC TWP RGE 10 34S 13W

PERMANENT DATUM	GROUND LEVEL	ELEVATION 1822 FT.	ELEVATIONS:
LOG MEASURED FROM	K.B. 9 FT.	ABOVE PERMANENT DATUM	KB 1831 FT.
DRILLING MEASURED FROM	K.B.		DF 1828 FT.
			CI 1822 FT.

DATE	15-FEB-90		
RUN NUMBER	ONE		
DEPTH-DRILLER	5100 FT.		
DEPTH-LOGGER	5100 FT.		
FIRST READING	5099 FT.		
LAST READING	2100 FT.		
CASING-DRILLER	392 FT.		
CASING-LOGGER	392 FT.		
BIT SIZE	7 7/8 INCH		
HOLE FLUID TYPE	OFL-CHEM		
DENS./VISC.	9.0 57		
PH/FLUID LOSS	2.5 10.8		
SAMPLE SOURCE	FLOWLINE		
RM @ MEAS TEMP	1.7 @ 60F		
RMF @ MEAS TEMP	.87 @ 60F		
RMC @ MEAS TEMP	1.87 @ 60F		
SOURCE RME/RMC	CALC. 1		
RM @ BHI	.9 @ 112F		
TIME SINCE CIRC	3.5 HRS		
MAX DEC TEMP	112F		
EQUIPMENT/BASE	V1006 LBL		
RECORDED BY	CHID PPS		
WITNESSED BY	MR. VEATCH		
WITNESSED BY			

RECEIVED
 STATE CORPORATION COMMISSION
 JAN 19 1996
 STATE CORPORATION COMMISSION