

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-173-20989-00-01 0001  
Spot: SWSENNW Sec/Twnshp/Rge: 12-26S-1W  
1085 feet from N Section Line, 2210 feet from W Section Line  
Lease Name: CORR A Well #: 4  
County: SEDGWICK Total Vertical Depth: 3340 feet

Operator License No.: 5030  
Op Name: VESS OIL CORPORATION  
Address: 1700 WATERFRONT PKWY BLDG 500  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2950		
CIBP		3270		
COND	13.375	74		75 SX
PROD	5.5	3336	2400	135 SX
SURF	8.625	263		150 SX
T1	2.875	2990		

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/16/2012 5:00 PM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: CASEY COATS Company: VESS OIL CORPORATION Phone: (316) 682-1537

Proposed Plugging Method: AS PER KCC RULES AND REGULATIONS

Plugging Proposal Received By: DAN FOX Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 08/16/2012 10:30 AM KCC Agent: DAN FOX

Actual Plugging Report:

ON 8/1/2012 CIBP SET @ 2950', RUN IN 4 SX CAP WITH BALER. ON 8/16/2012 PULLED UP TO 329' AND RAN 150 SX PLUG CIRC. TO SURFACE. PULLED 8 JOINTS OF 5.5" TOPPED OFF WITH 125 SX. FILLED WITH AN ADDITIONAL 56 SX DOWN 8.625", OPERATOR CAME BACK TO CUT OFF SURFACE CASING ABOUT 6' BELOW GROUND, WELDED A PLATE ON TOP. COPELAND ACID & CEMENT DID CEMENTING; 60/40 POS MIX W/4% GEL. JOB COMPLETE.

Perfs:

Top	Bot	Thru	Comments
3336	3340	CSG	
3004	3020	CSG	
3000	3020	CSG	

Remarks: COPELAND TICKET #C38612-IN

Plugged through: CSG

District: 02

Signed

Daniel R. Fox  
12/2/12 (TECHNICIAN)

RECEIVED  
NOV 29 2012

KCC WICHITA