

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-055-22186-00-00
Spot: SENWSWNE Sec/Twnshp/Rge: 24-22S-30W
1845 feet from N Section Line, 2112 feet from E Section Line
Lease Name: DOLL Well #: 1-24
County: FINNEY Total Vertical Depth: 4800 feet

Operator License No.: 5004
Op Name: VINCENT OIL CORPORATION
Address: 155 N MARKET STE 700
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	350		WITH 225 SX CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 11/17/2012 12:30 AM
Plug Co. License No.: 5929 Plug Co. Name: DUKE DRILLING CO., INC.
Proposal Rcvd. from: MIKE GODFREY Company: DUKE DRILLING CO., INC. Phone: (316) 267-1331

Proposed Plugging Method: 1ST PLUG AT 1920' WITH 50 SX CMT. 2ND PLUG AT 1110' WITH 80 SX CMT. 3RD PLUG AT 390' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN WitnessType: NONE
Date/Time Plugging Completed: 11/17/2012 2:30 AM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

Perfs:

1ST PLUG AT 1920' WITH 50 SX CMT. 2ND PLUG AT 1110' WITH 80 SX CMT. 3RD PLUG AT 390' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY ALLIED.

Plugged through: DP

District: 01

RECEIVED
NOV 20 2012
KCC DODGE CITY

Signed Kenny Sullivan
11/20/12 (TECHNICIAN)

RECEIVED
NOV 27 2012
KCC WICHITA