

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-23482-00-00
Spot: SWNWNENE Sec/Twnshp/Rge: 25-9S-24W
335 feet from N Section Line, 1310 feet from E Section Line
Lease Name: GOLTL Well #: 1-25
County: GRAHAM Total Vertical Depth: 4110 feet

Operator License No.: 30717
Op Name: DOWNING-NELSON OIL CO INC
Address: PO BOX 1019
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4109		150 SX
SURF	8.625	217		150 SX
T1	2.375	3962		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/21/2012 9:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: _____ Company: ALLIED CEMENT COMPANY Phone: (620) 793-5861

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement w/300# hulls and 11 sx gel.
Perforations @ 3912' - 3918' and 3863' - 3866'.
DV tool @ 2098' with 225 sx cement.

Plugging Proposal Received By: MARVIN MILLS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/21/2012 11:15 AM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Tied on to casing and pumped 75 sx cement w/200 # hulls followed by 11 sx gel followed by 215 sx cement. Hole standing full.
Tied on to back side and squeezed with 15 sx cement. Shut in pressure 200 psi.

Perfs:


Top	Bot	Thru	Comments
3912	3918		
3863	3866		

Remarks: ALLIED CEMENTING TICKET # 56065

Plugged through: CSG

District: 04

Signed


(TECHNICIAN)

CM

RECEIVED
DEC 03 2012

KCC WICHITA