

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-26387-00-00
Spot: SWSENWSW Sec/Twnshp/Rge: 8-15S-19W
1640 feet from S Section Line, 4300 feet from E Section Line
Lease Name: MOORE POND Well #: 1
County: ELLIS Total Vertical Depth: 3700 feet

Operator License No.: 4787
Op Name: TDI, INC.
Address: 1310 BISON RD
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3697	1987.5	150 SX
SURF	8.625	1252		375 SX

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 11/15/2012 8:00 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: BRETT HILDEBRAND Company: TDI INC. Phone: (785) 871-7311

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement w/700 # hulls.
Perforations: 3614' - 3618', 3625' - 3627', 3462' - 3466', 3319' - 3322' and 3204'.

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/15/2012 5:30 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Rigged to 5 1/2" casing and pumped 50 sx cement w/150 # hulls. Displaced plug to 3100'.
Shot casing at 2334'. Casing would not come loose. Shot casing at 1987.5' and pulled casing
loose to 1861'. Rigged to casing and pumped 150 sx cement w/300 # hulls.
Pulled casing to 1263' and pumped 25 sx cement w/100 # hulls.
Pulled casing to 500' and pumped 25 sx cement w/100 # hulls.
Pulled casing to 375' and pumped 50 sx cement w/50 # hulls to circulate cement to surface.
Pulled casing. Topped off 8 5/8" casing with 15 sx cement. Hole standing full.

Perfs:

Top	Bot	Thru	Comments
3614	3627		
3462	3466		
3319	3322		
3204	3204		

RECEIVED
NOV 29 2012
KCC WICHITA

Remarks: SWIFT SERVICES TICKET # 21966

Plugged through: CSG

District: 04

Signed


(TECHNICIAN)

CM

NOV